

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-083-21468-00-00
Spot: NESESE Sec/Twnshp/Rge: 5-21S-21W
960 feet from S Section Line, 330 feet from E Section Line
Lease Name: SHORTRIDGE Well #: 1
County: HODGEMAN Total Vertical Depth: 2455 feet

Operator License No.: 31093
Op Name: BECKER OIL CORPORATION
Address: PO BOX 1150
PONCA CITY, OK 74602

String	Size	Depth (ft)	Pulled (ft)	Comment
CIBP		2400		
PROD	4.5	2464	0	WITH 450 SX CMT
SURF	8.625	227		WITH 145 SX CMT

\$ 79.79

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 07/11/2007 11:40 AM
Plug Co. License No.: 99996 Plug Co. Name: ALLIED CEMENT COMPANY
Proposal Rcvd. from: DOUG BROWN Company: BECKER OIL Phone: (620) 287-4724

Proposed Plugging Method: MIX 500# HULLS WITH CEMENT 60/40 POZMIX, 6% GEL, FILL WITH CEMENT FROM 2354' TO SURFACE AND FILL SURFACE PIPE WITH CEMENT (TOTAL CEMENT 150 SKS+)

Plugging Proposal Received By: MICHAEL MAIER Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 07/11/2007 1:00 PM KCC Agent: MICHAEL MAIER

Actual Plugging Report:

CMT WAS CIRCULATED TO SURFACE WITH 450 SX CMT. PUMP 500# HULLS AND 130 SX CMT. PRESSURED TO 500# & HELD. BACKSIDE WAS FULL. COULD NOT PUMP IN TO.

Perfs:

Top	Bot	Thru	Comments
2423	2435		
2343	2354		
2309	2322		
2291	2299		

INVOICED


DATE 7-24-07

INV. NO. 2008060159

Remarks: USED 60/40 POZMIX 6% GEL BY ALLIED.

Plugged through: CSG

District: 01



Signed

Michael Maier
(TECHNICIAN)

RECEIVED

JUL 19 2007

KCC WICHITA

Form CP-2/3

[Handwritten initials]