

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-159-19091-00-01
Spot: W2NWSE Sec/Twnshp/Rge: 21-19S-10W
1980 feet from S Section Line, 1980 feet from E Section Line
Lease Name: HEINE Well #: 1
County: RICE Total Vertical Depth: 3305 feet

Operator License No.: 3911
Op Name: RAMA OPERATING CO., INC.
Address: 101 S. MAIN
STAFFORD, KS 67578

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	4.5	3291		
SURF	8.625	195		

\$ 107.41

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 06/18/2007 9:00 AM
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.
Proposal Rcvd. from: MIKE KELSO Company: MIKE'S TESTING & SALVAGE, INC Phone: (620) 562-8088

Proposed Plugging Method: SEE BELOW

Plugging Proposal Received By: VIRGIL CLOTHIER Witness Type: NONE
Date/Time Plugging Completed: 06/18/2007 1:00 PM KCC Agent: VIRGIL CLOTHIER

Actual Plugging Report:

PERFORATE @ 1250', 900', AND 250'. RUN TUBING TO 3130' AND PUMP 50 SX'S CEMENT WITH 100#'S COTTON HULLS. PULL TUBING TO 2200' AND PUMP 50 SX'S CEMENT WITH 100#'S HULLS. PULL TUBING TO 1250' AND PUMP 50 SX'S CEMENT. PULL TUBING TO 900' AND PUMP 35 SX'S CEMENT. PULL TUBING TO 250' AND CIRCULATE CEMENT TO SURFACE. CONNECTED ON TO 4.5" AND SQUEEZED 25-30 SX'S AT 200#'S. USED 335 SX'S CEMENT.

Perfs:

INVOICED
DATE 7-25-07
INV. NO. 2008060171

Remarks: 60-40 POZ, 4% GEL. COPELAND #C32479, LOG TEC #4968.

Plugged through: TBG

District: 02

Signed Virgil Clothier
(TECHNICIAN)

RECEIVED
KANSAS CORPORATION COMMISSION Form CP-2/3

JUL 24 2007

CONSERVATION DIVISION
WICHITA, KS

PT