

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-159-02255-00-00

Spot: SWSENE

Sec/Twnshp/Rge: 29-19S-9W

2970 feet from S Section Line,

990 feet from E Section Line

Lease Name: TOURNEAR

Well #: 2

County: RICE

Total Vertical Depth: 3220 feet

Operator License No.: 30364 •

Op Name: RESOURCE OPERATIONS, INC.

Address: BOX 9487

TULSA, OK 74157

String	Size	Depth (ft)	Pulled (ft)	Comment
COND	15.5	161		250 SX CMT.
PROD	8.625	3187		350 SX CMT.

\$104.65

Well Type: OIL

UIC Docket No:

Date/Time to Plug: 06/28/2007 8:45 AM

Plug Co. License No.: 31529

Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.

Proposal Rcvd. from: MIKE KELSO

Company: MIKE'S TESTING & SALVAGE, INC Phone: (620) 562-8088

Proposed
Plugging
Method:

SEE BELOW

Plugging Proposal Received By: VIRGIL CLOTHIER

WitnessType: PARTIAL

Date/Time Plugging Completed: 06/28/2007 11:30 AM

KCC Agent: VIRGIL CLOTHIER

Actual Plugging Report:

Perfs:

SAND OPEN HOLE TO 3130' - RETAGGED SAND, THEN CAPPED WITH 8 SX'S CEMENT. PERFORATE AT 1200', 800', AND 250'. RUN TUBING TO 1200' AND PUMP 75 SX'S CEMENT WITH 100#'S COTTON HULLS. PULL TUBING TO 800' AND PUMP 75 SX'S CEMENT WITH 50#'S COTTON HULLS. PULL TUBING TO 250 AND CIRCULATE CEMENT TO SURFACE. RUN 1" TUBING GOWN BACKSIDE OF 8.625" TO 250' AND CIRCULATE CEMENT TO SURFACE. USED TOTAL OF 350 SX'S CEMENT AND 250 #'S COTTON HULLS.

INVOICED
DATE 7-25-07
INV. NO. 2008060173

Remarks: 60-40 POZ, 4% GEL. COPELAND #C32492. LOG TECH #4984.

Plugged through: TBG

District: 02

Signed

Virgil Clothier

(TECHNICIAN)

RECEIVED
KANSAS CORPORATION COMMISSION Form CP-2/3

JUL 24 2007

CONSERVATION DIVISION
WICHITA, KS

[Signature]