

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-191-19036-00-00
Spot: NENESE Sec/Twnshp/Rge: 27-34S-2E
2129 feet from S Section Line, 340 feet from E Section Line
Lease Name: NORRISH Well #: 31
County: SUMNER Total Vertical Depth: 3520 feet

Operator License No.: 6044
Op Name: STELBAR OIL CORPORATION, INC.
Address: 1625 N WATERFRONT PARKWAY
WICHITA, KS 67206

String	Size	Depth (ft)	Pulled (ft)	Comment
COND	20	75		
PROD	5.5	3494		
SURF	10	1958		

\$ 114.40

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 06/22/2007 10:00 AM

Plug Co. License No.: 6044 Plug Co. Name: STELBAR OIL CORPORATION, INC.

Proposal Revd. from: ROBBIE Company: STELBAR OIL CORP. Phone: (316) 264-8378

Proposed Plugging Method: PIPE FOUND IN HOLE 20" @ 75', 10" UNK", 8" UNK, 7" UNK 5.5" @ 3494. SET CIBP AT 3437', REC 1000' OF 5.5 CASING. COULDN'T RECOVER 10", 8" OR 7". PERFORATED @ 266'. TIED ALL STRING OF PIPE TOGETHER AND CIRCULATED CMT BETWEEN ALL STRINGS OF PIPE CMT CIRC GOOD.

Plugging Proposal Received By: STEVE VANGIESON

WitnessType: COMPLETE (100%)

Date/Time Plugging Completed: 06/26/2007 11:30 AM

KCC Agent: STEVE VANGIESON

Actual Plugging Report:

Perfs:

THE 7", 8" AND 10" CASINGS WERE PERFORATED AT 250'. THE 10" AND 8" WERE WIELDED TOGETHER. THE 8" AND THE 7" WERE WIELDED TOGETHER. VALVES WERE WIELDED BETWEEN EACH. ALL VALVES WERE OPENED AND WE PUMPED WATER DOWN THE 7" CASING, WATER CIRCULATED THROUGH ALL STRINGS OF PIPE, AND ALSO UP THE 20". WE DECIDED TO TIE ON TO THE 10" AND 8". CMT WAS CIRC, BETWEEN THE 8" AND 10" AND ALSO UP THE 20". AFTER THESE STRINGS WERE CIRCULATED WITH CMT, WE TIED ON TO THE 7" AND 8" AND PUMPED CMT BETWEEN THESE AND BACK UP THE 7" CASING. CHECK CMT ON MONDAY AND FOUND CMT HAD FALLEN 20' IN THE 20" AND 110' IN THE 7" CASING, THE CMT TRUCK WERE CALLED BACK TO LOCATION ON TUESDAY THE 26TH AND THESE TWO SRINGS WERE TOPPED OFF WITH CMT.


INVOICED
DATE 7-25-07
INV. NO. 2008060174

Remarks: CONSOLIDATED CMT 60/40% GEL, A TOTAL OF 539 SKS CMT

Plugged through:

District: 02

Signed



(TECHNICIAN)

RECEIVED
KANSAS CORPORATION COMMISSION Form CP-2/3

JUL 24 2007

CONSERVATION DIVISION
WICHITA, KS

