

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-077-20637-00-00
Spot: W2SEW Sec/Twnshp/Rge: 17-31S-8W
3271 feet from S Section Line, 3757 feet from E Section Line
Lease Name: WARREN Well #: 2
County: HARPER Total Vertical Depth: 4498 feet

Operator License No.: 33168
Op Name: WOOLSEY OPERATING COMPANY, LL
Address: 125 N. MARKET, SUITE 1000
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	4.5	4493		75 SX
SURF	8.625	219		225 SX

\$ 146.19

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 06/25/2007 9:00 AM
Plug Co. License No.: 5105 Plug Co. Name: CLARKE CORPORATION
Proposal Rcvd. from: CARL W DURR Company: WOOLSEY OPERATING Phone: (620) 886-5606

Proposed Plugging Method: SPLIT IN CASING AT 3793', DRLG MUD IN HOLE. PERFS 4432'-4440', SET CIBP AT 3780' AND 2 SKS, 35 SKS 1400', 35 SKS 950' CIRC CMT 270'-0'.

Plugging Proposal Received By: STEVE VANGIESON Witness Type: PARTIAL
Date/Time Plugging Completed: 06/25/2007 10:15 AM KCC Agent: STEVE VANGIESON

Actual Plugging Report:

A CIBP WAS SET AT 3780' AND CAPPED WITH 2 SKS OF CMT. THE CASING WAS RECOVERED FROM 2800' AND PULLED FROM THE WELLBORE. 2 3/8" TUBING WAS RUN TO 1400', WHERE 35 SKS OF CMT WAS SPOTTED. THE TUBING WAS PULLED TO 950'. WHERE 35 SKS OF CMT WAS SPOTTED. THE TUBING WAS PULLED TO 270', WHERE CMT WAS CIRC TO SURFACE.

Perfs:

Top	Bot	Thru	Comments
4432	4440		


INVOICED
DATE 7-25-07
INV. NO. 2008060176

Remarks: ALLIED CMTG 37510 60/40 4% GEL -98.21954, 37.34976

Plugged through: OH

District: 02

Signed



(TECHNICIAN)

RECEIVED Form CP-2/3
KANSAS CORPORATION COMMISSION

JUL 24 2007

CONSERVATION DIVISION
WICHITA, KS

PKS