

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-077-21283-00-00
Spot: N2SWNW Sec/Twnshp/Rge: 17-31S-8W
3702 feet from S Section Line, 4677 feet from E Section Line
Lease Name: WARREN Well #: 3
County: HARPER Total Vertical Depth: 4526 feet

Operator License No.: 33168
Op Name: WOOLSEY OPERATING COMPANY, LL
Address: 125 N. MARKET, SUITE 1000
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	5.5	4524		100 SX
SURF	8.625	228		190 SX

147.10

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 06/21/2007 10:30 AM
Plug Co. License No.: 5105 Plug Co. Name: CLARKE CORPORATION
Proposal Rcvd. from: CARL W DURR Company: WOOLSEY OPERATING Phone: (620) 886-5606

Proposed Plugging Method: CIBP @ 4404' & 2 SKS CMT. RECOVER CASING. 35 SKS 1400', 35 SKS 950'. CIRC CMT 280'-0'.

Plugging Proposal Received By: VIRGIL CLOTHIER Witness Type: PARTIAL
Date/Time Plugging Completed: 06/21/2007 11:15 AM KCC Agent: STEVE VANGIESON

Actual Plugging Report:

A CIBP WAS SET AT 4404' AND CAPPED WITH 2 SKS OF CMT. THE CASING WAS RECOVERED FROM 3200' AND PULLED FROM THE WELLBORE. TUBING WAS RUN OPEN END TO 1400'. WHERE 35 SKS OF CMT WAS SPOTTED. THE TUBING WAS PULLED TO 950', WHERE 35 SKS OF CMT WAS SPOTTED. THE TUBING WAS PULLED TO 280', WHERE CMT WAS CIRC TO SURFACE. THE TUBING WAS PULLED FROM THE WELLBORE AND THE CMT WAS TOPPED OFF. -098.21911, 37.35095.

Perfs:

Top	Bot	Thru	Comments
4436	4442		

INVOICED
DATE 7-25-07
INV. NO. 2008060176

Remarks: ALLIED CMTG 60/40 POZ 4% GEL TICKET #24918

Plugged through: OH

District: 02

Signed 
(TECHNICIAN)

RECEIVED
KANSAS CORPORATION COMMISSION Form CP-2/3
JUL 24 2007
CONSERVATION DIVISION
WICHITA, KS

ll

