

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-163-01571-00-00  
Spot: S2NESW Sec/Twnshp/Rge: 21-9S-18W  
1526 feet from S Section Line, 3300 feet from E Section Line  
Lease Name: WIDMAN Well #: 1  
County: ROOKS Total Vertical Depth: 3590 feet

Operator License No.: 5030  
Op Name: VESS OIL CORPORATION  
Address: 1700 WATERFRONT PARKWAY, BLDG  
WICHITA, KS 67206

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	5.5	3581	0	w/150 sxs cmt
SURF	8.625	1435	0	w/450 sxs cmt

\$ 116.68

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 07/13/2007 10:00 AM  
Plug Co. License No.: 99998 Plug Co. Name: COMPANY TOOLS  
Proposal Rcvd. from: JOEL STULL Company: VESS OIL CORPORATION Phone: (316) 682-1537

Proposed Plugging Method: 07/13/2007 - Ordered out 425 sxs 60/40 pozmix - 10% gel -1200# hulls.  
07/16/2007 - Ordered out 425 sxs 60/40 pozmix - 10% gel -1200# hulls.  
Fluid level 900'. Bad casing from 1480' - 2032'.  
Unable to get below 2032'. Decided to P/A.

Plugging Proposal Received By: RICHARD WILLIAMS WitnessType: COMPLETE (100%)  
Date/Time Plugging Completed: 07/16/2007 10:30 AM KCC Agent: RICHARD WILLIAMS

Actual Plugging Report:

07/13/2007  
Ran tubing to 2032'.  
Allied pumped 80 bbls drilling mud, followed with 150 sxs 60/40 pozmix - 10% gel with 300# hulls.  
Pulled tubing to 1500'.  
Allied pumped 275 sxs cement with 900# hulls - good circulation out 5 1/2" casing and 8 5/8".  
Ran out of cement. PTOH.  
07/16/2007  
Ran tubing inside 5 1/2" - tagged cement at 940'.  
Backside 8 5/8" on vacuum.  
Allied pumped 100 sxs 60/40 pozmix - circulated with cement.  
PTOH. Topped off with 5 sxs cement and 300# hulls.  
Hooked up to backside and pumped 5 sxs cement.  
S.I.P. 400#.

Perfs:

**INVOICED**  
DATE 7-26-07  
INV. NO. 2008060189

Remarks: ALLIED CEMENTING COMPANY.

Plugged through: TBG

District: 04

Signed

*Richard Williams*

(TECHNICIAN)

RECEIVED  
KANSAS CORPORATION COMMISSION  
Form CP-2/3

JUL 25 2007

JUL 17 2007

CONSERVATION DIVISION  
WICHITA, KS

*PJT*