

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-159-20078-00-00  
Spot: NENESW Sec/Twnshp/Rge: 1-21S-7W  
2310 feet from S Section Line, 2970 feet from E Section Line  
Lease Name: BROTHERS Well #: 2  
County: RICE Total Vertical Depth: 3489 feet

Operator License No.: 4419  
Op Name: BEAR PETROLEUM, INC.  
Address: PO BOX 438  
HAYSVILLE, KS 67060

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	4.5	3485		75 SX
SURF	8.625	175		125 SX

\$ 113.39

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 07/17/2007 2:45 PM  
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.  
Proposal Rcvd. from: MIKE KELSO Company: MIKE'S TESTING & SALVAGE Phone: (620) 562-8088

Proposed Plugging Method: SEE BELOW

Plugging Proposal Received By: VIRGIL CLOTHIER Witness Type: PARTIAL  
Date/Time Plugging Completed: 07/17/2007 4:15 PM KCC Agent: VIRGIL CLOTHIER

Actual Plugging Report:

SAND OPEN HOLE TO 3435' & CAP WITH 4 SX'S CEMENT, CUT OFF CASING @ 1318' & PULL TO 1075' & PUMP 35 SX'S CEMENT, PULL CASING TO 625' & PUMP 35 SX'S CEMENT, PULL CASING TO 250' & CIRCULATE CEMENT TO SURFACE.

Perfs:

Top	Bot	Thru	Comments
3476	3489		OPEN HOLE

INVOICED

DATE 7-25-07

INV. NO. 2008060106

Remarks: 60-40 POZ, 4% GEL. COPELAND TICKET #C-32082

Plugged through: CSG

District: 02

Signed Virgil Clothier  
(TECHNICIAN)

RECEIVED  
KANSAS CORPORATION COMMISSION Form CP-2/3

JUL 24 2007

CONSERVATION DIVISION  
WICHITA, KS