

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-159-20073-00-00⁰¹
Spot: NENE Sec/Twnshp/Rge: 1-21S-7W
3960 feet from S Section Line, 330 feet from E Section Line
Lease Name: BROTHERS Well #: 1-1
County: RICE Total Vertical Depth: 3503 feet

Operator License No.: 4419
Op Name: BEAR PETROLEUM, INC.
Address: PO BOX 438
HAYSVILLE, KS 67060

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	4.5	3486	1300	
SURF	8.625	162		

\$113.85

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 07/13/2007 2:00 PM
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.
Proposal Rcvd. from: MIKE KELSO Company: MIKE'S TESTING & SALVAGE, INC Phone: (620) 938-2943

Proposed Plugging Method: SEE BELOW

Plugging Proposal Received By: MICHAEL WILSON Witness Type: NONE
Date/Time Plugging Completed: 07/13/2007 4:00 PM KCC Agent: VIRGIL CLOTHIER

Actual Plugging Report:

SAND TO 3435' & CAP WITH 4 SX'S CEMENT. CUT OFF CASING @ 1300' & PULL TO 1050' & PUMP 35 SX'S CEMENT, PULL CASING TO 625' & PUMP 35 SX'S CEMENT, PULL CASING TO 250' & CIRCULATE CEMENT TO SURFACE. USED 205 SX'S TOTAL.

Perfs:

INVOICED
DATE 7-25-07
INV. NO. 2008060166

Remarks: 60-40 POZ, 4% GEL. COPELAND TICKET C-32080

Plugged through: CSG

District: 02

Signed Virgil Clothier
(TECHNICIAN)

RECEIVED Form CP-2/3
KANSAS CORPORATION COMMISSION

JUL 24 2007

CONSERVATION DIVISION
WICHITA, KS

PT