

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-159-02280-00-00
Spot: NESENE Sec/Twnshp/Rge: 32-19S-9W
3630 feet from S Section Line, 330 feet from E Section Line
Lease Name: WALLACE Well #: 3
County: RICE Total Vertical Depth: 3224 feet

Operator License No.: 31528
Op Name: KELSO, MIKE OIL, INC.
Address: PO BOX 467
CHASE, KS 67524

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	5.5	3214		
SURF	8.625	238		

\$ 104.78

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 06/21/2007 9:30 AM
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.
Proposal Rcvd. from: MIKE KELSO Company: MIKE KELSO OIL, INC. Phone: (620) 562-8088

Proposed Plugging Method: SEE BELOW

Plugging Proposal Received By: VIRGIL CLOTHIER Witness Type: PARTIAL
Date/Time Plugging Completed: 06/21/2007 1:30 PM KCC Agent: VIRGIL CLOTHIER

Actual Plugging Report:

5.5" CASING PARTED @ 262'-RAN 5.5" BACK DOWN REJOINING PARTED 5.5" WITH A JOINT OF 7". RAN TUBING BACK DOWN ENCOUNTERING ROUGH SPOTS AT 300' AND 772'. POWER SWIVELLED ON DOWN TO 1071' AND GOT OUT OF CASING. PUMPED APPROX. 300 SX'S CEMENT WITH CALCIUM CHLORIDES AND COTTON HULLS-HAD GOOD RETURNS, COT CIRCULATION. RETAGGED CEMENT AFTER 1.25 HRS - TOP AT 520'. PUMPED 175 SX'S CEMENT AT 300' - NO CEMENT RETURNS. RE-TAGGED 6-22-2007 AT 120' INSIDE 5.5" AND 210' IN SURFACE. TOPPED OFF WITH 25 SX'S.

Perfs:

INVOICED
DATE 7-25-07
INV. NO. 2008060168

Remarks: COMMON CEMENT - COPELAND #C32483

Plugged through: TBG

District: 02

Signed Virgil Clothier
(TECHNICIAN)

RECEIVED
KANSAS CORPORATION COMMISSION

JUL 24 2007

Form CP-2/3

CONSERVATION DIVISION
WICHITA, KS

PKT