

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-065-01575-00-01  
Spot: NWSENE Sec/Twnshp/Rge: 34-9S-23W  
3650 feet from S Section Line, 1098 feet from E Section Line  
Lease Name: LAW B Well #: 2  
County: GRAHAM Total Vertical Depth: 4235 feet

Operator License No.: 5363  
Op Name: BEREXCO, INC.  
Address: PO BOX 20380  
WICHITA, KS 67208

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	5.5	4235	0	500 SX
SURF	8.625	209	0	125 SX

\$ 137.64

Well Type: EOR UIC Docket No: E25293.2 Date/Time to Plug: 07/19/2007 9:00 AM  
Plug Co. License No.: 5363 Plug Co. Name: BEREXCO, INC.  
Proposal Rcvd. from: BOB GRANT Company: BEREXCO, INC. Phone: (785) 628-6101

Proposed Plugging Method: Ordered 400 sxs 60/40 pozmix - 10% gel - 800# hulls.

Plugging Proposal Received By: BRUCE BASYE WitnessType: COMPLETE (100%)  
Date/Time Plugging Completed: 07/19/2007 2:00 PM KCC Agent: MARVIN MILLS

Actual Plugging Report:

Ran tubing in to 3674' - pumped 150 sxs cement with 500# hulls.  
Pulled tubing to 1763' - pumped 135 sxs cement with 200# hulls - good circulation of cement.  
Pulled tubing out - tied onto backside - pressured up to 400# P.S.I.  
Tied onto the 5 1/2" - squeezed with 20 sxs cement with 50# hulls.  
S.I.P. 500#.

Perfs:

Top	Bot	Thru	Comments
4134	4140		MARMATON
3738	3960		L-KC
3726	3732		TOR

**INVOICED**  
DATE 7-30-07  
INV. NO. 2008060191

RECEIVED  
KANSAS CORPORATION COMMISSION

JUL 26 2007

Remarks: ALLIED CEMENTING COMPANY-TICKET #31694.

Plugged through: TBG

District: 04

Signed *Marvin Mills*

(TECHNICIAN)

JUL 23 2007

*PET*

SKELLY OIL COMPANY

#2 LAW

34-9-23W  
NW SE NE

22

Contr. \_\_\_\_\_ GRAHAM County

E. 2457 Comm. \_\_\_\_\_ Comp. 10-12-51 IP 1422 BOPD (LANS)

DRAW DOWN

Tops	Depth	Datum
LANS	3746	-1289
CONG	4067	-1610
ARB	4211	-1754
T.D.	4236	-1779

Casing

8" 210

5" 4235

PB 4148:

PERF 3831-32:

450' OIH & 2000'

WTR: SQZ: PB 3750

PERF 36 S, 3738-42

CO 3786:

PERF 72 S, 3770-78

LAW POOL

+	+	+
+	+	+
+	+	+

INDEPENDENT OIL & GAS SERVICE  
WICHITA, KANSAS