

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-135-24674-00-00
Spot: SENE Sec/Twnshp/Rge: 4-20S-24W
1790 feet from N Section Line, 760 feet from E Section Line
Lease Name: FILBERT 'ER' Well #: 1-4
County: NESS Total Vertical Depth: 4440 feet

Operator License No.: 5086
Op Name: PINTAIL PETROLEUM, LTD.
Address: 225 N MARKET STE 300
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comment
SURF	8.625	211		WITH 150 SX CMT

\$ 144.30

Well Type: DH UIC Docket No: _____ Date/Time to Plug: 07/24/2007 10:00 AM
Plug Co. License No.: 5123 Plug Co. Name: PICKRELL DRILLING COMPANY, INC.
Proposal Rcvd. from: MIKE KERNS Company: PICKRELL DRILLING COMPANY, I Phone: (316) 262-8427

Proposed Plugging Method: 1ST PLUG AT 1620' WITH 50 SX CMT. 2ND PLUG AT 780' WITH 80 SX CMT. 3RD PLUG AT 240' WITH 40 SX CMT. 4TH PLUG AT 60' WITH 20 SX CMT. 5TH PLUG TO CIRCULATE RAT HOLE WITH 15 SX CMT. NO MOUSE HOLE.

Plugging Proposal Received By: ERIC MACLAREN WitnessType: NONE
Date/Time Plugging Completed: 07/24/2007 11:00 AM KCC Agent: ERIC MACLAREN

Actual Plugging Report:

1ST PLUG AT 1620' WITH 50 SX CMT. 2ND PLUG AT 780' WITH 80 SX CMT. 3RD PLUG AT 240' WITH 40 SX CMT. 4TH PLUG AT 60' WITH 20 SX CMT. 5TH PLUG TO CIRCULATE RAT HOLE WITH 15 SX CMT. NO MOUSE HOLE.

Perfs:

INVOICED
DATE 8-1-07
INV. NO. 2008060203

RECEIVED
KANSAS CORPORATION COMMISSION


JUL 27 2007

CONSERVATION DIVISION
WICHITA, KS

Remarks: USED 60/40 POZMIX 6% GEL 1/4# FLO SEAL BY ALLIED.

Plugged through: DP

District: 01



Signed Eric MacLaren
(TECHNICIAN)

[Signature]

[Signature]