

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-129-21802-00-00

Spot: S2NE

Sec/Twnshp/Rge: 31-33S-41W

1980 feet from N Section Line,

1320 feet from E Section Line

Lease Name: ELKHART FOREST

Well #: 31 #1 5600

County: MORTON

Total Vertical Depth: -650 feet

KCC
PICT
7/30/07
Per
District

Operator License No.: 5278

String Size Depth (ft) Pulled (ft) Comment

SURF 8.625 1692

WITH 495 SX CMT

Op Name: EOG RESOURCES, INC.

Address: 3817 NW EXPRESSWAY, SUITE 500
OKLAHOMA CITY, OK 73112

\$ 182.00

Well Type: DH

UIC Docket No:

Date/Time to Plug: 07/11/2007 10:00 PM

Plug Co. License No.: 30684

Plug Co. Name: ABERCROMBIE RTD, INC

Proposal Rcvd. from: LARRY TAYLOR

Company: EOG RESOURCES

Phone: (405) 246-3100

Proposed Plugging Method: 1ST PLUG AT 1725' WITH 50 SX CMT. 2ND PLUG AT 500' WITH 50 SX CMT. 3RD PLUG AT 60' WITH 20 SX CMT. 4TH PLUG TO CIRCULATE RAT HOLE WITH 15 SX CMT. 5TH PLUG TO CIRCULATE MOUSE HOLE WITH 10 SX CMT.

Plugging Proposal Received By: JIM HOLLAND

WitnessType: NONE

Date/Time Plugging Completed:

KCC Agent: JIM HOLLAND

Actual Plugging Report:

Perfs:

1ST PLUG AT 1792' WITH 200 SX CMT. TOC TAGGED AT 955'. 2ND PLUG AT 500' WITH 50 SX CMT. 3RD PLUG AT 60-0' WITH 20 SX CMT. 4TH PLUG TO CIRCULATE RAT HOLE WITH 15 SX CMT. 5TH PLUG TO CIRCULATE MOUSE HOLE WITH 10 SX CMT. ***BLM CHANGED BOTTOM PLUG FROM 50 SX CMT TO 200 SX CMT.***

INVOICED

DATE 7-30-07

INV. NO. 2008060192

RECEIVED
KANSAS CORPORATION COMMISSION


JUL 26 2007

CONSERVATION DIVISION
WICHITA, KS

Remarks: USED 60/40 POZMIX 6% GEL 2% CC BY HALLIBURTON.

Plugged through: DP

District: 01



Signed

Jim Holland PICT III
(TECHNICIAN)

Form SP-2/3

PICT