

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-109-20469-00-00  
Spot: SENENW Sec/Twnshp/Rge: 3-12S-34W  
4321 feet from S Section Line, 3112 feet from E Section Line  
Lease Name: REB Well #: 2  
County: LOGAN Total Vertical Depth: 4769 feet

Operator License No.: 5363

Op Name: BEREXCO, INC.

Address: PO BOX 20380  
WICHITA, KS 67208

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	4.5	4768	0	225 SX
SURF	8.625	343	0	250 SX

\$ 154.99

Well Type: EOR

UIC Docket No: E25511.2

Date/Time to Plug: 07/17/2008 10:00 AM

Plug Co. License No.: 3152

Plug Co. Name: POE SERVICING INC

Proposal Rcvd. from: MARK LEIKER

Company: BEREXCO, INC.

Phone: (785) 628-6101

Proposed Plugging Method: Ordered 300 sxs 60/40 pozmix - 10% gel - 600# hulls.  
Plug thru tubing.

Plugging Proposal Received By: HERB DEINES

Witness Type: COMPLETE (100%)

Date/Time Plugging Completed: 07/17/2007 2:50 PM

KCC Agent: DARREL DIPMAN

**Actual Plugging Report:**

8 5/8" surface casing set at 343' w/250 sxs cement.  
4 1/2" production casing set at 4768' w/225 sxs cement.  
TD 4769' original PBTD 4640'.  
DV tool at 2678' w/650 sxs cwc - #1 CIBP at 4318'.  
Perforations open from 4239' - 4248'.  
Perforations below CIBP: 4337' 4340' - #2 CIBP set at 4640'.  
Perforations below CIBP: 4670' 4675 and 4706' - 4720'.  
Ran tubing to 4270' - pumped 125 sxs cement with 400# hulls.  
Pulled tubing to 2584' - pumped 100 sxs cement with 200# hulls.  
Pulled tubing to 1253' - pumped 40 sxs cement - cement to surface.  
Pulled tubing to surface.  
Connected to 4 1/2" production casing - pumped 25 sxs cement.  
Max. P.S.I. 250#. S.I.P. 100#.  
Connected to 8 5/8" surface pipe - pumped 2 sxs cement.  
Max. P.S.I. 500# S.I.P. 200#.

**Perfs:**

Top	Bot	Thru	Comments
7406	7420		
4670	4675		
4337	4340		
4239	4248		

**INVOICED**  
DATE 8-3-07  
INV. NO. 2008060209

RECEIVED  
KANSAS CORPORATION COMMISSION

JUL 30 2007

Remarks: ALLIED CEMENTING COMPANY-TICKET #33239.

Plugged through: TBG

CONSERVATION DIVISION  
WICHITA, KS

District: 04

HD

Signed

Darrel Dipman


(TECHNICIAN)

Form CP-2/3

JUL 20 2007

PKT

STATE KANS COUNTY LOGAN RE-ISSUE 3-12S-34W  
 FIELD ELAINE (LANSING/CHEROKEE) SE NE NW  
 OPER BEREN CORP 4290FSL 2970FEL SEC  
 WELL 2 R.E.B. WELL CLASS IW  
 API 15-109-20469-0000 STATUS WI-O  
 SPUD 12/19/1988 COMP 01/17/1989  
 DTD 4770 LTD FTD CHEROKEE PBTD 4640



LOC 4 3/4 MI SE PAGE, KS Petroleum Information Corporation

IP D&A (CONVERTED TO WATER INJECTION WELL) EL: 3220 KB 3215 GR  
 INJ ZONE: CHEROKEE 4670-4720 GROSS

LOG TOPS:		
HEEBNER	4100	-880
LANSING I	4335	-1115
BSE KANSAS CITY	4431	-1211
PAWNEE	4573	-1353
FT SCOTT	4631	-1411
CHEROKEE	4660	-1440
TD	4770	-1550

CSGS: 8 5/8 @ 343 W/ 250 SACKS  
 4 1/2 @ 4769 W/ 225 SACKS  
 DV TOOL @ 2678 W/600 SX  
 TBGS: 2 3/8 @ 4290 W/ PKR  
 DRLG COMP 12/31/88 RIG REL 12/31/88

DSTS: DST 1 4287-4360 TORONTO/LANSING  
 REC 10 FT OIL 105 FT SOCWM 180 FT MCW  
 INIT OP 30M IFP 106 FFP 122  
 FINAL OP 1H IFP 155 FFP 216  
 ISIP 1160 30M FSIP 1147 1H  
 DST 2 4363-4400 LANSING  
 REC 30 FT SOCM 184 FT MCW W/OIL SPKS 1 TR OIL 92 FT MCW  
 INIT OP 45M IFP 76 FFP 106  
 FINAL OP 45M IFP 161 FFP 188  
 ISIP 1123 45M FSIP 1123 45M

KS R5-040991 CONTINUED Copyright 1991 Petroleum Information Corporation

KS R5-040991 BEREN CORP 2 R.E.B.

DSTS: DST 3 4655-4770 FT SCOTT/CHEROKEE  
 REC 2 FT OIL 113 FT HOCM  
 INIT OP 45M IFP 106 FFP 111  
 FINAL OP 45M IFP 131 FFP 135  
 ISIP 1417 45M FSIP 1374 45M

PERFS: CHEROKEE PERF W/ 48/IT 4670-4720 GROSS  
 4670-4675 4706-4720  
 ACID 1500 GALS 20% HCL 1000 GALS 15% HCL  
 TSTG RESULTS NOT RPTD  
 BRPG @ 4640  
 LANSING PERF W/ 4/FT 4337-4340  
 ACID 500 GALS 15% HCL 1500 GALS 28% HCL

NO CORES

OPER ADDRESS: 970 4TH FINANCIAL CTR, WICHITA, KS 67202

CONTR: BEREDCO INC GEOL: SAM HOUSTON

ID CHANGES: STATUS CHGD FROM W-INJ

REISSUE TO: CORRECT STATUS, FORMATION @ TD  
 ADD DSTS, LOG TOPS, PROD CSG, TBG, PERFS, TREATMENT, PBTD

REPLACEMENT FOR CARD ISSUED 1/31/89