

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-033-20700-00-00  
Spot: NESW Sec/Twnshp/Rge: 32-34S-19W  
1980 feet from S Section Line, 3300 feet from E Section Line  
Lease Name: WOOLFOLK Well #: 1  
County: COMANCHE Total Vertical Depth: 5400 feet

Operator License No.: 30931  
Op Name: DAYSTAR PETROLEUM, INC.  
Address: 1321 W. 93 N. PO BOX 360  
VALLEY CENTER, KS 67147

| String | Size  | Depth (ft) | Pulled (ft) | Comment         |
|--------|-------|------------|-------------|-----------------|
| COND   | 20    | 92         |             | GROUT           |
| PROD   | 4.5   | 5398       | 3003        | WITH 300 SX CMT |
| SURF   | 8.625 | 456        |             | WITH 280 SX CMT |

\$ 175.5

Well Type: GAS UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 07/26/2007 9:45 AM  
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.  
Proposal Rcvd. from: STEVE BODINE Company: DAYSTAR PETROLEUM Phone: (620) 793-2757

Proposed Plugging Method: SAND BACK TO 5250' & 4 SX CMT. PLUG AT 900' WITH 50 SX CMT. PLUG AT 500' WITH 50 SX CMT. PLUG AT 250' WITH 30 SX CMT. PLUG AT 40' WITH 10 SX CMT

Plugging Proposal Received By: KEN JEHLIK Witness Type: COMPLETE (100%)  
Date/Time Plugging Completed: 07/26/2007 11:30 AM KCC Agent: JERRY W. STAPLETON

Actual Plugging Report:

SAND BACK TO 5250' & 4 SX CMT WITH DUMP BAILER. 1ST PLUG AT 900' WITH 15 SX GEL & 50 SX CMT. 2ND PLUG AT 500' WITH 50 SX CMT. 3RD PLUG AT 250' WITH 30 SX CMT. 4TH PLUG AT 40' WITH 10 SX CMT.

Perfs:


| Top  | Bot  | Thru | Comments |
|------|------|------|----------|
| 5304 | 5310 |      |          |

**INVOICED**  
DATE 8-3-07  
INV. NO. 2008060216

Remarks: USED 60/40 POZMIX 6% GEL BY COPELAND ACID.

Plugged through: CSG

District: 01



Signed

Jerry W. Stapleton  
(TECHNICIAN)  
PIET II

RECEIVED  
KANSAS CORPORATION COMMISSION  
JUL 30 2007  
CONSERVATION DIVISION  
WICHITA, KS