

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-207-27131-00-00
Spot: SWSESWSE Sec/Twnshp/Rge: 24-23S-16E
165 feet from S Section Line, 1815 feet from E Section Line
Lease Name: SAFERITE-60 Well #: 9-B
County: WOODSON Total Vertical Depth: 715 feet

Operator License No.: 30102

Op Name: CHRIESTENSON, ROBERT DBA C & S O

Address: PO BOX 41
NEOSHO FALLS, KS 66758

String	Size	Depth (ft)	Pulled (ft)	Comment
SURF	7	40	0	

\$ 35.00

Well Type: LH

UIC Docket No:

Date/Time to Plug: 07/09/2007 10:00 AM

Plug Co. License No.: 31440

Plug Co. Name: CONSOLIDATED OIL WELL SERVICES, INC

Proposal Rcvd. from: ROBERT CHRIESTENSON Company: CONSOLIDATED OIL WELL SERVI Phone: (620) 963-2342

Proposed
Plugging
Method:

THIS WELL CONSISTED OF AN UNCASD BORE TO 715'. AT 715' THE DRILL BIT DISINTIGRATED AND THE WELL WAS LOST. THE PLUGGING PROPOSAL WAS TO PLACE A 50' CEMENT PLUG AT 715' AND TO CIRCULATE THE WELL FULL OF CMEENT FROM 300' TO SURFACE.

Plugging Proposal Received By: CLAYTON TITEL

WitnessType: NONE

Date/Time Plugging Completed: 07/09/2007 12:00 AM

KCC Agent: CLAYTON TITEL

Actual Plugging Report:

Perfs:

PIPE WAS RAN INTO THE WELL TO 700'. 10 SACKS OF CEMENT WERE PUMPED THROUGH THE PIPE TO 700'. THE PIPE WAS PULLED TO 300'. CEMENT WAS PUMPED INTO THE 1" PIPE UNTIL CEMENT CIRCULATED FROM THE SURFACE CASING AT SURFACE. THE PIPE WAS REMOVED. DISPLACEMENT WAS FILLED FROM SURFACE.

RECEIVED
KCC DISTRICT #3

JUL 18 2007 CPT

CHANUTE, KS

INVOICED
DATE 8-3-07
INV. NO. 2008060210

Remarks:

Plugged through: TBG

District: 03

Signed

Clayton P. Titel

(TECHNICIAN)

RECEIVED
KANSAS CORPORATION COMMISSION Form CP-2/3

JUL 30 2007

CONSERVATION DIVISION
WICHITA, KS

PCT