

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-185-10457-00-02  
Spot: NWNWNW Sec/Twnshp/Rge: 27-24S-13W  
330 feet from N Section Line, 330 feet from W Section Line  
Lease Name: MCNAUGHTEN B Well #: 1  
County: STAFFORD Total Vertical Depth: 4091 feet

Operator License No.: 33582  
Op Name: DAR ENERGY LLC  
Address: 300 SW 93RD ST.  
OKLAHOMA CITY, OK 73139

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	7	4077	0	WITH 200 SX CMT
SURF	12.5	412		WITH 400 SX CMT

\$132.96

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 07/10/2007 8:30 AM  
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.  
Proposal Rcvd. from: RICHARD MCINTYRE Company: QUALITY WELL SERVICE, INC. Phone: (620) 786-2001

Proposed Plugging Method: PLUGGING PROPOSAL SAME AS ACTUAL PLUGGING REPORT.

Plugging Proposal Received By: RICHARD LACEY Witness Type: COMPLETE (100%)  
Date/Time Plugging Completed: 07/10/2007 10:50 AM KCC Agent: RICHARD LACEY

**Actual Plugging Report:**

ANHYDRITE = 800'. HOLE HAD FILL TO ABOVE PERFS AT 3650'. SAND TO 3600' & 7 SX CMT WITH DUMP BAILER. PERFORATED 7" AT 800'. RAN TUBING TO 800'. PUMPED 275 SX CMT DOWN TUBING. CIRCULATED CMT UP 7". GOOD CIRCULATION UP 12 1/2" X 7" BUT NO CMT. PULLED TUBING. PUMPED DOWN 7" WITH 175 SX CMT CIRCULATING CMT UP 12 1/2" X 7" ANNULUS.

**Perfs:**


Top	Bot	Thru	Comments
3732	3737		
3718	3727		

**INVOICED**  
DATE 8-3-07  
INV. NO. 2008060212

Remarks: USED 60/40 POZMIX 6% GEL BY COPELAND.

Plugged through: TBG

District: 01



Signed

*Richard W. Lacey*

(TECHNICIAN)

RECEIVED  
KANSAS CORPORATION COMMISSION  
Form CP-2/B  
JUL 30 2007  
CONSERVATION DIVISION  
WICHITA, KS

*PKT*