

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-001-01962-00-00  
Spot: NESESE Sec/Twnshp/Rge: 3-26S-18E  
825 feet from S Section Line, 495 feet from E Section Line  
Lease Name: NORTH FINNEY Well #: 26  
County: ALLEN Total Vertical Depth: 800 feet

Operator License No.: 33221  
Op Name: ROXANNA PIPELINE, INC.  
Address: 4600 GREENVILLE AVE., SUITE 200  
DALLAS, TX 75206

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	800	3	0	
SURF	7	20	0	\$ 35.00

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 07/21/2007 10:00 AM  
Plug Co. License No.: 5491 Plug Co. Name: W & W PRODUCTION COMPANY, GENERAL PARTNERSHIP  
Proposal Rcvd. from: TOM GILBERT Company: ROXANNA PIPELINE, INC. Phone: (214) 691-6216

Proposed Plugging Method: THIS WELL CONSISTED OF 2 7/8" CAING TO APPROXIMATELY 800' THAT HAD BEEN CEMENTED IN FROM BOTTOM TO TOP. THE PLUGGING PROPOSAL WAS TO SQUEEZE THE 2 7/8" CASING FULL OF CEMENT FROM SURFACE.

Plugging Proposal Received By: CLAYTON TITEL WitnessType: NONE  
Date/Time Plugging Completed: 07/21/2007 10:45 AM KCC Agent: CLAYTON TITEL

Actual Plugging Report:

THE PUMP TRUCK WAS CONNECTED DIRECTLY TO THE 2 7/8" CASING. COTTON SEED HULLS WERE MIXED WITH THE FIRST OF THE CEMENT TO BE PUMPED. CEMENT WAS PUMPED INTO THE 2 7/8" CASING UNTIL THE WELL WOULD HOLD PRESSURE. THE WELL WAS THEN SHUT IN AT 750 PSI. 37 SACKS OF CEMENT WERE PUMPED INTO THIS WELL.

Perfs:

RECEIVED  
KCC DISTRICT #3

JUL 25 2007 CPT

CHANUTE, KS

INVOICED  
DATE 8-3-07  
INV. NO. 2008060223

Remarks: THIS WELL WAS GPS'D AS NO.NFI 18 AT 806' NSL & 562' WEL OF S. 3.

Plugged through: CSG

District: 03

Signed Clayton P. Titel  
(TECHNICIAN)

RECEIVED  
KANSAS CORPORATION COMMISSION Form CP-2/3

JUL 30 2007

CONSERVATION DIVISION  
WICHITA, KS

PKT