

RECEIVED
KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING APPLICATION
Please TYPE Form and File ONE Copy

AUG 10 2007

Form CP-1
September 2003
This Form must be Typed
Form must be Signed
All blanks must be Filled

API # 15-035-20898-00-00 (Identifier Number of this well). This must be listed for wells drilled since 1967; if no API # was issued, indicate original spud or completion date 11-28-75.

Well Operator: R.R. Abderhalden KCC License #: 5394
(Owner / Company Name) (Operator's)

Address: 100 S. Main, Suite 510 City: Wichita

State: Kansas Zip Code: 67202 Contact Phone: (316) 262-3411

Lease: Werner Well #: 3 Sec. 31 Twp. 32 S. R. 6 East West

NE - SW - SE Spot Location / QQQQ County: Cowley

1022 ^{9/0} Feet (in exact footage) From North / South (from nearest outside section corner) Line of Section (Not Lease Line)

1720 ^{16/50} Feet (in exact footage) From East / West (from nearest outside section corner) Line of Section (Not Lease Line)

Per GPS - KCC-Dig

Check One: Oil Well Gas Well D&A Cathodic Water Supply Well

SWD Docket # _____ ENHR Docket # _____ Other: _____

Conductor Casing Size: _____ Set at: _____ Cemented with: _____ Sacks

Surface Casing Size: 8 5/8 Set at: 170 ft Cemented with: 100 Sacks

Production Casing Size: 4 1/5 Set at: 3149 Cemented with: 75 Sacks

List (ALL) Perforations and Bridgeplug Sets: 3124-30; 3052-56; 3070-74; all perforations plugged with 48 gals. sand and 13 sax cement. PBTD 1890. New perforations 1857-69

Elevation: 1308 (G.L. / K.B.) T.D.: 3150 PBTD: 1890 Anhydrite Depth: _____
(Stone Corral Formation)

Condition of Well: Good Poor Casing Leak Junk in Hole

Proposed Method of Plugging (attach a separate page if additional space is needed): Set a 50 ft cement plug on bottom. Shoot off casing and pull. Run tubing to 350 ft and cement to surface.

Is Well Log attached to this application as required? Yes No Is ACO-1 filled? Yes No

If not explain why? NA

Plugging of this Well will be done in accordance with K.S.A. 55-101 et. seq. and the Rules and Regulations of the State Corporation Commission.

List Name of Company Representative authorized to be in charge of plugging operations: Dwain Stout

100 S. Main, Suite 510 Phone: (316) 262-3411

Address: _____ City / State: Wichita, KS

Plugging Contractor: RRA., Inc. KCC License #: 5656
(Company Name) (Contractor's)

Address: 100 S. Main, Suite 510, Wichita, KS Phone: (316) 262-3411

Proposed Date and Hour of Plugging (if known?): 8-15-07 Appr.

Payment of the Plugging Fee (K.A.R. 82-3-118) will be guaranteed by Operator or Agent

Date: 8-10-07 Authorized Operator / Agent: R.R. Abderhalden
(Signature)

Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202

DRILLERS' LOG

AUG 10 2007

CONSERVATION DIVISION
WICHITA, KS

R R A, INC.
No. 3 Werner
NE SW SE, Sec. 31-32S-6E
Cowley County, Kansas

Elev: 1308 K.B.

Commenced: 10-20-75
Completed: 10-25-75

Surface Casing: 168' of 8-5/8"
cemented w/75 sx common cement,
3% cc. 10-18-75

FORMATION

DEPTH

Surface Hole	0 - 170
Shale & Lime	170 - 2320
Sand	2320 - 2365
Shale & Lime	2365 - 2555
Lime & Shale	2555 - 2913
Shale & Lime	2913 - 3061
Lime	3061 - 3150 RTD

I do hereby certify that the foregoing statements are true and correct to the best of my knowledge and belief.

D N B DRILLING, INC.

James L. Donelson
JAMES L. DONELSON

STATE OF KANSAS: ss:

Subscribed and sworn to before me this 30th day of October, 1975.

Ella Priess

Ella Priess, Notary Public

<i>Ella Priess</i>
STATE NOTARY PUBLIC
Sedgwick County, Kansas
My Com. Expires Aug. 25, 1976



CORPORATION COMMISSION

Kathleen Sebelius, Governor Thomas E. Wright, Chairman Michael C. Moffet, Commissioner Joseph F. Harkins, Commissioner

NOTICE OF RECEIPT OF WELL PLUGGING APPLICATION (CP-1)

ABDERHALDEN, R. R.
510 HARDAGE CENTER
100 S MAIN
WICHITA, KS 67202

August 14, 2007

Re: WERNER #3
API 15-035-20898-00-00
31-32S-6E, 1022 FSL 1720 FEL
COWLEY COUNTY, KANSAS

Dear Operator:

This letter is to notify you that the Conservation Division has received your plugging proposal, form CP-1, for the above well and has reviewed the proposal for completeness. The central office will now forward your CP-1 to the district office listed below for review of the proposed plugging method. **Please contact the district office for approval of your proposed plugging method at least five (5) days before plugging the well, pursuant to K.A.R. 82-3-113(b). If a workover pit will be used during the plugging of the well it must be permitted. A CDP-1 form must be filed and approved prior to the use of the pit in accordance with K.A.R. 82-3-600.**

The Conservation Division's review of form CP-1, either in the central or district office, does not include an inquiry into well ownership or the filing operator's legal right to plug the well. This notice in no way constitutes authorization to plug the above well by persons not having legal rights of ownership or interest in the well.

This notice is void after February 10, 2008. The CP-1 filing does not bring the above well into compliance with K.A.R. 82-3-111 with regard to the Commission's temporary abandonment requirements.

Sincerely,

Steve Bond
Production Department Supervisor

District: #2
3450 N. Rock Road, Suite 601
Wichita, KS 67226
(316) 630-4000