

MAR 20 2000

CONSERVATION DIVISION  
Wichita, Kansas

SERVICE POINT:

DAKLEY

REMIT TO P.O. BOX 31  
RUSSELL, KANSAS 67665

15-039-20913-00-00

DATE <u>3-4-00</u>	SEC. <u>3</u>	TWP. <u>35</u>	RANGE <u>26W</u>	CALLED OUT	ON LOCATION <u>10:00 AM</u>	JOB START <u>12:00 PM</u>	JOB FINISH <u>2:00 PM</u>
LEASE <u>HEX</u>	WELL # <u>1-3</u>	LOCATION <u>OBERLIN 17E-3/4S-W INTO</u>			COUNTY <u>DECATUR</u>	STATE <u>KS</u>	
OLD OR <u>NEW</u> (Circle one)							

CONTRACTOR MURFIN DRUG. RIG #3

TYPE OF JOB PTA

HOLE SIZE 7 7/8" T.D. 3959'

CASING SIZE \_\_\_\_\_ DEPTH \_\_\_\_\_

TUBING SIZE \_\_\_\_\_ DEPTH \_\_\_\_\_

DRILL PIPE 4 1/2" DEPTH 2162'

TOOL \_\_\_\_\_ DEPTH \_\_\_\_\_

PRES. MAX \_\_\_\_\_ MINIMUM \_\_\_\_\_

MEAS. LINE \_\_\_\_\_ SHOE JOINT \_\_\_\_\_

CEMENT LEFT IN CSG. \_\_\_\_\_

PERFS. \_\_\_\_\_

DISPLACEMENT \_\_\_\_\_

OWNER SAME

CEMENT AMOUNT ORDERED 190 SKS 60/40 POZ 6806EL 1/4" FLO-SEAL

COMMON	<u>114</u>	<u>SKS</u>	@	<u>7.55</u>	<u>860.70</u>
POZMIX	<u>76</u>	<u>SKS</u>	@	<u>3.25</u>	<u>247.00</u>
GEL	<u>10</u>	<u>SKS</u>	@	<u>9.50</u>	<u>95.00</u>
CHLORIDE			@		
Flo-Seal	<u>48#</u>		@	<u>1.15</u>	<u>55.20</u>
			@		
			@		
			@		
			@		
HANDLING	<u>190</u>	<u>SKS</u>	@	<u>1.05</u>	<u>199.50</u>
MILEAGE	<u>44</u>	<u>PER SK/MI</u>			<u>585.20</u>

EQUIPMENT

PUMP TRUCK CEMENTER TERRY

# 300 HELPER WAYNE

BULK TRUCK

# 218 DRIVER LONNIE

BULK TRUCK

# \_\_\_\_\_ DRIVER \_\_\_\_\_

TOTAL 2,042.60

REMARKS:

25 SKS AT 2162'

100 SKS AT 1646'

40 SKS AT 351'

10 SKS AT 40'

15 SKS RAT HOLE

THANK YOU

SERVICE

DEPTH OF JOB 2162'

PUMP TRUCK CHARGE 470.00

EXTRA FOOTAGE @ 23100

MILEAGE 77 miles @ 3.00 231.00

PLUG 8 5/8 DRY HOLE @ 23.00

TOTAL 724.00

CHARGE TO: MURFIN DRUG. CO, INC.

STREET \_\_\_\_\_

CITY \_\_\_\_\_ STATE \_\_\_\_\_ ZIP \_\_\_\_\_

FLOAT EQUIPMENT

\_\_\_\_\_ @ \_\_\_\_\_

\_\_\_\_\_ @ \_\_\_\_\_

\_\_\_\_\_ @ \_\_\_\_\_

\_\_\_\_\_ @ \_\_\_\_\_

\_\_\_\_\_ @ \_\_\_\_\_

TOTAL \_\_\_\_\_

To Allied Cementing Co., Inc.  
You are hereby requested to rent cementing equipment and furnish cementer and helper to assist owner or contractor to do work as is listed. The above work was done to satisfaction and supervision of owner agent or contractor. I have read & understand the "TERMS AND CONDITIONS" listed on the reverse side.

TAX \_\_\_\_\_

TOTAL CHARGE \_\_\_\_\_

DISCOUNT \_\_\_\_\_ IF PAID IN 30 DAYS

SIGNATURE [Signature]

PRINTED NAME \_\_\_\_\_

15-039-2013-00-00

RECEIVED  
STATE CORPORATION COMMISSION

MAR 20 2000

CONSERVATION DIVISION  
Wichita, Kansas

**Hix #1-3**

1280 FEL 2080 FSL  
Sec. 3-T3S-R26W  
Decatur County, Kansas

**DST #1 3495-3554' (Tor, Lan A zones) 30-45-45-60;** IF: wk surface blow building to 3"; FF: wk surface blow building to 1"; Rec: 124' M w/ oil spts, 56' MW (40% W, 60% M) RW .17 @ 82°, 38,000 PPM CHL; HP: 1571-1619; SI: 1189-1168; FP: 23/57, 64/104; BHT: 98°.

**DST #2 3550-3571' (Lan C - Pollnow zones) 30-30-30-30,** IF: weak ¼" blow throughout, FF: weak ¼" blow throughout; Rec: 60' MW w/show of free oil on top (85% W, 15% M), RW .16 @ 70°, 48,000 PPM CHL; HP: 1744-1699; SI: 1170-1146; FP: 20/39, 40/59; BHT: 97°.

**DST #3 3572-3612 (LKC D, E/F) 30-45-45-60,** IF: wk blow building to 5"; FF: wk blow building to 1"; Rec. 10' cl o, 180' oil sptd w, 292' w, 482' TF; 28° gravity; 70,000 PPM CHL; RW .11 @ 70° HP: 1769-1711; SI: 1173-1132; FP: 22/130, 135/259; BHT: 103°.