

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-169-20204-00-00  
Spot: SWNWNE Sec/Twnshp/Rge: 32-16S-3W  
4034 feet from S Section Line, 2335 feet from E Section Line  
Lease Name: GIBSON Peterson Well #: 1A *KCC Per op 07*  
County: SALINE Total Vertical Depth: 3597 feet *On CP-1*

Operator License No.: 31934  
Op Name: CASEBEER, INC.  
Address: 909 N. HIGH DRIVE  
MCPHERSON, KS 67460

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	4.5	3591		
SURF	8.625	387		

\$ 116.90

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 08/16/2007 10:00 AM  
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.  
Proposal Rcvd. from: RICHARD MCINTYRE Company: QUALITY WELL SERVICE Phone: (620) 727-3410

Proposed Plugging Method: WELL HAD TUBING AND PACKER CEMENTED IN HOLE AT 1140'. ORDERS WERE TO PERFORATE CASING AT 1080' AND 430'. PUMP 35 SXS AT 1080' AND PUMP CEMENT TO CIRCULATE TO SURFACE FROM 430'.

Plugging Proposal Received By: GREG EVES Witness Type: COMPLETE (100%)  
Date/Time Plugging Completed: 08/16/2007 2:00 PM KCC Agent: GREG EVES

Actual Plugging Report:

PERFORATED CASING AT 1080' AND 430'. RAN TUBING TO 1080' AND PUMPED 35 SXS CEMENT. PULLED TUBING TO 450' AND PUMPED 85 SXS TO CIRCULATE TO SURFACE. PUMPED 20 SXS TO TOP OFF AFTER PULLING REMAINING TUBING.

Perfs:

INVOICED  
DATE 8-29-07  
INV. NO. 2008060319

RECEIVED  
KANSAS CORPORATION COMMISSION  
AUG 24 2007  
CONSERVATION DIVISION  
WICHITA, KS

Remarks: QUALITY WELL SERVICE, TICKET #1477, TOTAL = 130 SXS 60/40 POZ 4% GEL

Plugged through: TBG

District: 02

Signed Greg Eves  
(TECHNICIAN)

*PRE*