

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-051-06787-00-00
Spot: SWSESW Sec/Twnshp/Rge: 35-13S-20W
330 feet from S Section Line, 3630 feet from E Section Line
Lease Name: DREILING C Well #: 2
County: ELLIS Total Vertical Depth: 3840 feet

Operator License No.: 32875
Op Name: CWB - CO, A GENERAL PARTNERSHIP
Address: 40837 BEAR CREEK ROAD
SPRINGVILLE, CA 93265

| String | Size | Depth (ft) | Pulled (ft) | Comment |
|--------|-------|------------|-------------|---------|
| L1 | 2.875 | 3490 | 0 | 295 SX |
| PROD | 5.5 | 3835 | 0 | 150 SX |
| SURF | 8.625 | 1525 | 0 | 700 SX |

\$124.80

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 08/22/2007 9:00 AM
Plug Co. License No.: 99998 Plug Co. Name: COMPANY TOOLS
Proposal Rcvd. from: JAMES HERTEL Company: CWB-CO, A GENERAL PARTNERS Phone: (785) 628-2593

Proposed Plugging Method: Ordered 240 sxs 60/40 pozmix - 10% gel - 200# hulls.
Present perms 3830' - 3840'; 3802' - 3806'.
Fluid Level 2940'.

Plugging Proposal Received By: HERB DEINES WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 08/22/2007 10:00 AM KCC Agent: PAT STAAB

Actual Plugging Report:

Allied rigged to 2 7/8" tubing - pumped 50 sxs 60/40 pozmix neat, followed with 100 sxs 60/40 pozmix with 200# hulls mixed in.
Max. P.S.I. 1000#. S.I.P. 600#.
Rigged to 8 5/8" - pressured to 600# immediately.
Backside was full from previous squeeze.
Rigged to 5 1/2" casing - pumped 5 sxs 60/40 pozmix.
Max. P.S.I. 500#. S.I.P. 500#.

Perfs:

| Top | Bot | Thru | Comments |
|------|------|------|----------|
| 3636 | 3639 | | |
| 3508 | 3510 | | |

INVOICED

DATE 8-29-07
INV. NO. 2008060320

RECEIVED
KANSAS CORPORATION COMMISSION
AUG 23 2007
CONSERVATION DIVISION
WICHITA, KS

Remarks: ALLIED CEMENTING COMPANY-TICKET #33154.

Plugged through: TBG

District: 04

Signed _____

(TECHNICIAN)

AUG 22 2007

Handwritten initials/signature

7

SUNRAY OIL CORP #2 DREILING 'C' 35-13-20W
 SW SE SW

Contr. _____ ELLIS County

E. 2227 Comm. 9-18-45 Comp. 10-11-45 IP 347 BOPD

| Tops | Depth | Datum |
|------|-------|-------|
| ANH | 1513 | |
| HEEB | 3465 | |
| Co | 3505 | -1278 |
| LANS | 3526 | |
| B/KC | 3767 | |
| CONG | 3811 | |
| ARB | 3835 | |
| TD | 3842 | |

Casing
 8" 1525 or 316
 5" 3835

SO 3686-90: 350' OIL/2 hrs
 Swb 3½ BOPH: A/500
 Swb 10 BOPH/5 hrs

| | | | |
|--|--|--|--|
| | | | |
| | | | |
| | | | |

INDEPENDENT OIL & GAS SERVICE
 WICHITA, KANSAS