

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-195-21041-00-01
Spot: SESESENE Sec/Twnshp/Rge: 35-11S-22W
2879 feet from S Section Line, 163 feet from E Section Line
Lease Name: HILLMAN Well #: 7
County: TREGO Total Vertical Depth: 1777 feet

Operator License No.: 4767
Op Name: RITCHIE EXPLORATION, INC.
Address: 8100 E 22ND ST N # 700 BOX 783188
WICHITA, KS 67278

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	4.5	1803	0	500 SX
SURF	8.625	169	0	150 SX

\$57.75

Well Type: SWD UIC Docket No: D21146.0 Date/Time to Plug: 08/17/2007 8:30 AM
Plug Co. License No.: 6426 Plug Co. Name: EXPRESS WELL SERVICE & SUPPLY INC
Proposal Rcvd. from: TOM Company: RITCHIE EXPLORATION, INC. Phone: (316) 691-9500

Proposed Plugging Method: Ordered 150 sxs 60/40 pozmix - 10% gel - 500# hulls.

Plugging Proposal Received By: PAT STAAB Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 08/17/2007 10:45 AM KCC Agent: MARVIN MILLS

Actual Plugging Report:

Ran tubing into 1412' - pumped 50 sxs cement with 200# hulls.
Pulled tubing to 750' - pumped 20 sxs cement with 100# hulls - good circulation of cement.
Pulled tubing out - tied onto top - squeezed with 5 sxs cement.
Max. P.S.I. 500#. Held.
Backside full of cement.

Perfs:

Top	Bot	Thru	Comments
1442	1505		CEDAR HILLS

INVOICED
DATE 8/22/07
INV. NO. 2008060303

RECEIVED
KANSAS CORPORATION COMMISSION
AUG 21 2007
CONSERVATION DIVISION
WICHITA, KS

Remarks: ALLIED CEMENTING COMPANY-TICKET #33320.

Plugged through: TBG

District: 04

Signed 

(TECHNICIAN)


Form CP-2/3

AUG 20 2007

A. SCOTT RITCHIE
 125 N. MARKET, #950 #7 HILLMAN 35-11-22W
 WICHITA, KS 67202 230'E & 160'S,
 CONTR MURFIN DRUG. CO. CTY TREGO C SE SE NE

GEOLOGICAL FIELD SHAW CREEK EAST

E 2335 KB CM 7/5/82 CARD ISSUED 9/23/82 IP SWDW
 API 15-195-21,041 CED HILLS 1442-1505
 OA



SMP	Tops	Depth	Datum
	CED HILLS	1256 +	1079
	B CED HILLS	1508 +	827
	TD	1810 +	525

8 5/8 " 169/150SX, 4 1/2 " 1803/500SX
 NO DST'S
 MICT - CO, PF 1 / 1442, 1 / 1472, 1 / 1495, 1 / 1505, INJECTION
 RATE SATISFACTORY, SWDW

D21146.0

(NOTE: ORIGINALLY FIRST REPORTED AS 230'E&130'S, C SE SE NE)

INDEPENDENT OIL & GAS SERVICE
 WICHITA, KANSAS