

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-167-02407-00-01

Spot: S2SENE

Sec/Twnshp/Rge: 25-14S-13W

2923 feet from S Section Line,

970 feet from E Section Line

Lease Name: WILLSON

Well #: 1

County: RUSSELL

Total Vertical Depth: 2425 feet

Operator License No.: 31874

Op Name: MORRIS, BILL III DBA MORRIS OIL OP

Address: 19624 FOUR CORNERS ROAD
BUNKER HILL, KS 67626

String	Size	Depth (ft)	Pulled (ft)	Comment
--------	------	------------	-------------	---------

PROD	5.5	2974	0	150 SX
------	-----	------	---	--------

SURF	8.625	282	0	250 SX
------	-------	-----	---	--------

\$ 78.81

Well Type: EOR

UIC Docket No: E21965.1

Date/Time to Plug: 08/21/2007 8:00 AM

Plug Co. License No.: 32528

Plug Co. Name: FUNK, DAVID A. DBA OIL AND OPERATING SERVICES

Proposal Rcvd. from: BILL MORRIS

Company: MORRIS OIL OPERATIONS

Phone: (785) 483-9417

Proposed
Plugging
Method:

Ordered 250 sxs 60/40 pozmix - 10% gel - 300# hulls.

Plugging Proposal Received By: HERB DEINES

WitnessType: COMPLETE (100%)

Date/Time Plugging Completed: 08/21/2007 10:45 AM

KCC Agent: MARVIN MILLS

Actual Plugging Report:

Pumped 170 sxs 60/40 pozmix - 10% gel w/300# hulls down the top of the 5 1/2".
Max. P.S.I. 500#. S.I.P. 200#.
Checked backside - full of cement.

Perfs:

Top	Bot	Thru	Comments
2322	2327		
2247	2250		
2223	2226		

INVOICED

DATE 8-29-07

INV. NO. 2008060324

Remarks: QUALITY CEMENTING COMPANY-TICKET #1479.

Plugged through: CSG

District: 04

Signed

CM

(TECHNICIAN)


RECEIVED
KANSAS CORPORATION COMMISSION
Form CP-2/3

AUG 23 2007

CONSERVATION DIVISION

AUG 22 2007

4-125 MAP NO. _____ SEC. 25-14S-13W
 STATE Kans. COUNTY Russell LOC S/2 SE NE
 OPER Morris & Morris, Russell, Kansas FT/FR _____ LINE _____
 WELL #1 FARM Willson FT/FR _____ LINE _____
 POOL Hall-Gurney ELEV 1705 GR. 1707 DE 1710 KB _____
 CONT Shields Drlg. Tools GEOL Marvin Ratts
 CO INT. 2900' test
 F.R. 3/26/64 SPUD 3/24/64 COMP 4/21/64
 TD 2975 FM LKc PBTD 2550
 PRODUCING FM. FROM — TO PERF W/HOLES TREATMENT
Tarkio 2223 - 56 56 Frac
 P. Co. Pump: 25 BOPD + 60 BWPD, grav. not available



8-5/8" @ 281 w/150 sx.
 5 1/2" @ 2974 1/2 w/200 sx.

KB Spl Tops:							
Anh	655	+1055	Top	2566	- 856	LKc	2874 -1164
B/Anh	690	+1020	Hb	2797	-1087	RTD	2975 -1265
Tark	2162	- 452	Tor	2815	-1105		

No DST's, RTD 2975, LKc, No log, 5 1/2" @ 2974 1/2 w/200 sx., CO 2950, 24/2910-16, 12/2891-94 (LKc) HFW, PB 2780, 16/2763-67 (Top) HFW

Data Inc.