

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-065-23113-00-00
Spot: NWSWNW Sec/Twnshp/Rge: 27-6S-21W
3630 feet from S Section Line, 4950 feet from E Section Line
Lease Name: PENNINGTON Well #: 1
County: GRAHAM Total Vertical Depth: 3875 feet

Operator License No.: 32210
Op Name: SPRING, HARRY A.
Address: BOX 1788 911 W. BROADWAY
ARDMORE, OK 73402

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	5.5	3865	0	175 SX CMT.
SURF	8.625	238	0	175 SX CMT. #125.94

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 08/21/2007 12:00 AM
Plug Co. License No.: 99977 Plug Co. Name: QUALITY OIL WELL CEMENTING
Proposal Rcvd. from: MIKE DAVIGNON Company: SPRING, HARRY A. Phone: (785) 216-0016

Proposed Plugging Method: Ordered out 225 sxs 60/40 pozmix - 10% gel - 500# hulls - 15 sxs gel.
Port collar at 1920' w/350 sxs.

Plugging Proposal Received By: HERB DEINES WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 08/21/2007 1:00 PM KCC Agent: RICHARD WILLIAMS

Actual Plugging Report:

Quality Oil Well Cementing pumped 40 sxs 60/40 pozmix - 10% gel w/100# hulls, followed with 15 sxs gel spacer w/200# hulls, followed with 140 sxs cement with 200# hulls.
Max. P.S.I. 1000#. S.I.P. 900#.
Backside full of cement - instant 500#.

Perfs:

Top	Bot	Thru	Comments
3803	3809		

INVOICED
DATE 8-29-07
INV. NO. 2008060327

Remarks: QUALITY OIL WELL CEMENTING.

Plugged through: CSG

District: 04

Signed Richard Williams
(TECHNICIAN)

RECEIVED
KANSAS CORPORATION COMMISSION Form CP-2/3

AUG 23 2007

CONSERVATION DIVISION

AUG 22 2007

Handwritten initials

replacement card
WILDCAT

BLAKE EXPLORATION LLC
BOGUE KS 67625

27-06S-21W
NW SW NW

#1 PENNINGTON

site: 10 N & 1-1/4 E OF BOGUE KS
contr: AMERICAN EAGLE DRLG #3
geol: MICHAEL A. DAVIGNON

city: GRAHAM
field: WC (TOWN HALL WEST DISC)

API 15-065-23113

tr date 11/15/2005
spd date 01/07/2006
drig comp 01/15/2006
card issued 05/08/2006
last revised 04/02/2007

ELV: 2308 KB, 2301 GL LOG

	depth/datum
tops.....	1957 +351
ANH.....	3520 -1212
HEEB.....	3560 -1252
LANS.....	3738 -1430
BKC.....	3831 -1523
ARB.....	3875 -1567
RTD.....	

IP status
OIL, LKC 3803-3809, 02/27/2006
CORR & INFO REL: 4/2/2007 - CORR DATES & RTD (WAS 3865); WAS OIL WELL - TIGHT HOLE
CSG: 8-5/8" 238 / 175 SX (ALT 2), 5-1/2" 3865 / 175 SX, PORT COLLAR AT 1926 / 350 SX
COMMENT: MI & RURT 1/5/2006; DELAYED SPD
NO CORES
4 DSTS TAKEN - DETAILS NA
TRGT ZN: GRAN (OIL), PTD 3750 (GRAN), MICT - CO, PF (LKC) 3803-3809, W / 4 SPF, AC 250 GAL (MA), SWB LD, GSO, SET 5-1/2" TBG AT 3750, NO PKR, POP, OIL WELL (POTENTIAL NOT RPTD), 2/27/2006 - NO OTHER INFO AVAILABLE

COPYRIGHT 2006
INDEPENDENT OIL & GAS SERVICE, INC.
WICHITA, KANSAS