

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-115-20872-00-00⁰¹
Spot: SWNESE Sec/Twnshp/Rge: 10-18S-1E
1616 feet from S Section Line, 987 feet from E Section Line
Lease Name: W SCULLY Well #: 2-10
County: MARION Total Vertical Depth: 3330 feet

Operator License No.: 5920
Op Name: BANDY, TERRY P. DBA TE-PE OIL & G
Address: PO BOX 522
CANTON, KS 67428

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	5.5	3329	1500	PTKCC
SURF	8.25	202		

\$ 108.23

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 08/10/2007 11:30 AM
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.
Proposal Rcvd. from: RICHARD MCINTYRE Company: QUALITY WELL SERVICE Phone: (620) 727-3410

Proposed Plugging Method: SAND TO 50' ABOVE TOP PERFS (3133') AND CAP WITH 5 SXS CEMENT. CIRCULATE WITH CEMENT FROM 300' TO SURFACE.

Plugging Proposal Received By: MICHAEL WILSON Witness Type: PARTIAL
Date/Time Plugging Completed: 08/10/2007 2:00 PM KCC Agent: GREG EVES

Actual Plugging Report:

SANDED TO 3080' AND CAPPED WITH 5 SXS CEMENT. PULLED PIPE TO 330' AND PUMPED 90 SXS CEMENT TO CIRCULATE TO SURFACE.

Perfs:

INVOICED
DATE 8-29-07
INV. NO. 2008060329

RECEIVED
KANSAS CORPORATION COMMISSION

AUG 24 2007

CONSERVATION DIVISION
WICHITA, KS

Remarks: UNITED CEMENTING, TICKET #7946, TOTAL = 90 SXS 60/40 POZ 4% GEL

Plugged through: CSG

District: 02

Signed Greg Eves
(TECHNICIAN)

PTKCC