

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-159-21846-00-00  
Spot: SESWSW Sec/Twnshp/Rge: 26-18S-10W  
330 feet from S Section Line, 4290 feet from E Section Line  
Lease Name: GODFREY Well #: 6  
County: RICE Total Vertical Depth: 3309 feet

Operator License No.: 5141  
Op Name: ZENITH DRILLING CORPORATION  
Address: PO BOX 780428  
WICHITA, KS 67278

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	5.5	3308		150 SX CMT
SURF	8.625	262		150 SX CMT

\$ 107.54

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 08/14/2007 2:00 PM  
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.  
Proposal Rcvd. from: MIKE KELSO Company: MIKE'S TESTING & SALVGE, INC. Phone: (620) 562-8088

Proposed Plugging Method: SEE BELOW

Plugging Proposal Received By: DUANE KRUEGER Witness Type: PARTIAL  
Date/Time Plugging Completed: 08/14/2007 4:00 PM KCC Agent: VIRGIL CLOTHIER

Actual Plugging Report:

SAND OPEN HOLE TO 3150' & CAP WITH 5 SX'S CEMENT, CUT OFF CASING @ 2019' & PULL TO 1200' & PUMP 35 SX'S CEMENT WITH 100 LBS COTTON HULLS, PULL CASING TO 850' & PUMP 35 SX'S WITH 100 LBS COTTON HULLS, PULL CASING TO 310' & CIRCULATE CEMENT TO SURFACE.

Perfs:

Top	Bot	Thru	Comments
3274	3277		
3253	3254		
3238	3241		

**INVOICED**  
DATE 8-29-07  
INV. NO. 2008060330

RECEIVED  
KANSAS CORPORATION COMMISSION

AUG 24 2007

CONSERVATION DIVISION  
WICHITA, KS

Remarks: 60-40 POZ, 4% GEL. COPELAND TICKET #C-32473. USED 245 SX'S TOTAL.

Plugged through: CSG

District: 02

Signed Virgil Clothier  
(TECHNICIAN)

*Handwritten initials*