

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 30 days from plugging date.

KANSAS CORPORATION COMMISSION  
OIL & GAS CONSERVATION DIVISION  
WELL PLUGGING RECORD  
K.A.R. 82-3-117

Form CP-4  
September 2003  
Type or Print on this Form  
Form must be Signed  
All blanks must be Filled

Lease Operator: Daystar Petroleum, Inc.  
Address: 1321 W. 93rd N. Valley Center, KS  
Phone: (316) 755-3523 Operator License #: 30931  
Type of Well: Gas Docket #: \_\_\_\_\_  
(Oil, Gas D&A, SWD, ENHR, Water Supply Well, Cathodic, Other) (If SWD or ENHR)  
The plugging proposal was approved on: \_\_\_\_\_ (Date)  
by: Jerry Stapleton (KCC District Agent's Name)  
Is ACO-1 filed?  Yes  No If not, is well log attached?  Yes  No  
Producing Formation(s): List All (If needed attach another sheet)  
\_\_\_\_\_  
Depth to Top: \_\_\_\_\_ Bottom: \_\_\_\_\_ T.D. \_\_\_\_\_  
\_\_\_\_\_  
Depth to Top: \_\_\_\_\_ Bottom: \_\_\_\_\_ T.D. \_\_\_\_\_  
\_\_\_\_\_  
Depth to Top: \_\_\_\_\_ Bottom: \_\_\_\_\_ T.D. \_\_\_\_\_

API Number: 15 - 033-20700 - 00-00  
Lease Name: Woolfolk  
Well Number: 1  
Spot Location (OOQQ): \_\_\_\_\_ C \_\_\_\_\_ NE \_\_\_\_\_ SW  
1980 Feet from \_\_\_\_\_ North /  South Section Line  
3300 Feet from  East / \_\_\_\_\_ West Section Line  
Sec. 32 Twp. 34 S. R. 19 \_\_\_\_\_ East  West  
County: Comanche  
Date Well Completed: 10/10/1986  
Plugging Commenced: 7/24/07  
Plugging Completed: 7/26/07

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface Conductor & Production)			
Formation	Content	From	To	Size	Put In / Pulled Out
				8 5/8"	456' / none
				4 1/2"	5398' / 3002'

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed. from \_\_\_\_\_ feet to \_\_\_\_\_ feet each set.  
Cut 8 5/8" head & 4 1/2" casing off. Checked hole & found bottom @ 5100'. Sanded bottom & found bottom @ 5000' & dumped 4sxs. cement. Ran knife to 3002', casing came loose. Pulled 2072' stopping @ 730'. Pumped 15sxs. gel & 50sxs. cement @ 900'. Pulled 430' stopping @ 500', pumped 50sxs. cement. Pulled 250' out, stopping @ 250', pumped 35sxs. cement. Pulled 250' out ran 40' back in hole. Circulated 10sxs. cement to the top.

Name of Plugging Contractor: Mike's Testing & Salvage, Inc. License #: 31529  
Address: P.O. Box 467 Chase, Kansas 67524  
Name of Party Responsible for Plugging Fees: Daystar Petroleum, Inc.  
State of Kansas County: Rice ss.  
RECEIVED  
KANSAS CORPORATION COMMISSION  
AUG 08 2007  
CONSERVATION DIVISION  
WICHITA, KS


Mike Kelso (Employee of Operator) or (Operator) on above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.  
(Signature) Mike Kelso

(Address) P.O. Box 467 Chase, Kansas 67524

SUBSCRIBED and SWORN TO before me this 7th day of August, 20 07

Irene Herzberg  
Notary Public

My Commission Expires: \_\_\_\_\_



Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202

PKT