

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 30 days from plugging date.

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING RECORD
K.A.R. 82-3-117

Form CP-4
September 2003
Type or Print on this Form
Form must be Signed
All blanks must be Filled

Lease Operator: Lebsack Oil Production
Address: P.O. Box 489 Hays, Ks
Phone: (785) 625-5444 Operator License #: 5210
Type of Well: Gas Docket #: _____
(Oil, Gas D&A, SWD, ENHR, Water Supply Well, Cathodic, Other) (If SWD or ENHR)
The plugging proposal was approved on: _____ (Date)
by: Virgal Cothier (KCC District Agent's Name)
Is ACO-1 filed? Yes No If not, is well log attached? Yes No
Producing Formation(s): List All (if needed attach another sheet)
_____ Depth to Top: _____ Bottom: _____ T.D. _____
_____ Depth to Top: _____ Bottom: _____ T.D. _____
_____ Depth to Top: _____ Bottom: _____ T.D. _____

API Number: 15 - 159-22445 -00-00
Lease Name: Axtell B KCC Pkt Per CP213 8/16/07
Well Number: 1
Spot Location (OQQQ): Senene Pkt 8/16/07
750 Feet from North / South Section Line
200 Feet from East / West Section Line
Sec. 13 Twp. 21S S. R. 9 East West
County: Rice
Date Well Completed: 1/12/05
Plugging Commenced: 7-24-07
Plugging Completed: 7-25-07

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface Conductor & Production)				
Formation	Content	From	To	Size	Put In	Pulled Out
				8 5/8"	284'	None
				5 1/2"	3435'	2320'

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed, from _____ feet to _____ feet each set.

Sanded bottom to 3250' w/ 5 sx. cement. Rigged up floor & pulled slips. Rigged up casing knife & cut casing @ 2568'. pipe not loose. Came up to 2460' & cut casing, not loose. Came up to 2320' & cut casing loose. Pulled up to 1150', rigged up Copeland & pumped 35sx. w/ 100 hulls @ 1150'. Pulled up to 750' & pumped 35sx. w/ 100 hulls. Pulled up to 335' & circulated cement w/ 150sx. 60/40 Poz. 4%gel

Name of Plugging Contractor: Mike's Testing & Salvage, Inc. License #: 31529 RECEIVED
Address: P.O. Box 467 Chase, Kansas 67524 KANSAS CORPORATION COMMISSION

Name of Party Responsible for Plugging Fees: Lebsack Oil Production, Inc. AUG 08 2007

State of Kansas County, Rice ss. Mike Kelso (Employee of Operator) or (Operator) on above-described well, being first duly

sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

(Signature) Mike Kelso
(Address) P.O. Box 467 Chase, Kansas 67524

SUBSCRIBED and SWORN TO before me this 7th day of August, 2007

Irene Herzberg
Notary Public

My Commission Expires: _____
NOTARY PUBLIC - State of Kansas
IRENE HERZBERG
My Appt. Exp. 8-24-09

Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202

PK