

AUG 09 2007

Form CP-4
December 2003

Notice: Fill out COMPLETELY
and return to Conservation Division
at the address below within
60 days from plugging date.

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING RECORD
K.A.R. 82-3-117

CONSERVATION DIVISION
WICHITA, KS
Form must be Signed
All blanks must be Filled

Lease Operator: Anderson Energy, Inc.
Address: 221 S. Broadway, Suite 302 Wichita, KS 67202
Phone: (316) 263-1006 Operator License #: 6484
Type of Well: oil Docket #: _____
(Oil, Gas D&A, SWD, ENHR, Water Supply Well, Cathodic, Other) (If SWD or ENHR)
The plugging proposal was approved on: 6/26/07 (Date)
by: Marvin Miller (KCC District Agent's Name)
Is ACO-1 filed? Yes No If not, is well log attached? Yes No
Producing Formation(s): List All (If needed attach another sheet)
Arbuckle Depth to Top: 3703.5 Bottom: 3709 T.D. 3709

Depth to Top: _____ Bottom: _____ T.D. _____

Depth to Top: _____ Bottom: _____ T.D. _____

API Number: 15-051-24031-00-00
Lease Name: Pfannenstiel
Well Number: 9
Spot Location (QQQQ): N/2 - N/2 - NW/4 -
330 Feet from North / South Section Line
3960 Feet from East / West Section Line
Sec. 1 Twp. 15 S. R. 19 East West
County: Ellis
Date Well Completed: 11/1/1984
Plugging Commenced: 6/26/2007
Plugging Completed: 6/26/2007

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface Conductor & Production)				
Formation	Content	From	To	Size	Put In	Pulled Out
Arbuckle	Oil & Water	3703.5	3709	8-5/8"	604'	0
				5-1/2"	3704'	0

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.


Tubing to 2800' Pumped 125 sx 60/40 Poz, 10% Gel w/300# Hulls, Good circulation throughout. Pulled tubing to 1500' and pumped 110 sx 60/40 Poz, 10% Gel and 200# Hulls.
Cement Circulated. TOOH w/ tubing, hooked to swedge on casing and pumped 25 sx 60/40 Poz. Max pressure 500#. Shut-in pressure 300#.

Name of Plugging Contractor: Express Well Service & Supply, LLC License #: 6426
Address: 1110 Highway 40, Victoria, KS 67671-0019
Name of Party Responsible for Plugging Fees: Anderson Energy, Inc.
State of Kansas County, Sedgwick, ss.
William L. Anderson

(Employee of Operator) or (Operator) on above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

(Signature) William L. Anderson

(Address) 221 S. Broadway, #302 Wichita, KS 67202



Subscribed and SWORN TO before me this 8th day of August, 20 07

(Signature) Glynné Bolte My Commission Expires: 4-24-2011
Notary Public

PKT