

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

RECEIVED
KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING RECORD
 K.A.R. 82-3-117

AUG 13 2007

Form CP-4
 December 2003
 Type or Print on this Form
 Form must be Signed
 All blanks must be Filled

CONSERVATION DIVISION
 WICHITA, KS

Lease Operator: Trans Pacific Oil Corporation
 Address: 100 S Main, Suite 200, Wichita, KS 67202
 Phone: (316) 262-3596 Operator License #: 9408
 Type of Well: Oil Docket #: _____
 (Oil, Gas D&A, SWD, ENHR, Water Supply Well, Cathodic, Other) (If SWD or ENHR)
 The plugging proposal was approved on: _____ (Date)
 by: Hubert Deines (KCC District Agent's Name)
 Is ACO-1 filed? Yes No If not, is well log attached? Yes No
 Producing Formation(s): List All (If needed attach another sheet)
 _____ Depth to Top: _____ Bottom: _____ T.D. _____
 _____ Depth to Top: _____ Bottom: _____ T.D. _____
 _____ Depth to Top: _____ Bottom: _____ T.D. _____

API Number: 15 - 009-22, 147 - 00-00
 Lease Name: Hermes
 Well Number: 1
 Spot Location (QQQQ): _____ - NE - NE - SE
2310 Feet from North / South Section Line
330 Feet from East / West Section Line
 Sec. 18 Twp. 19 S. R. 12 East West
 County: Barton
 Date Well Completed: _____
 Plugging Commenced: 7-25-07
 Plugging Completed: 7-26-07

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface Conductor & Production)				
Formation	Content	From	To	Size	Put In	Pulled Out
				8 5/8	301	
				4 1/2	3536	1675

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

Sand at 3200', bailed 4 sacks, ripped pipe, 2400' left over, worked pipe, no gain, ripped 2100', no gain, had Perf-Tech shoot 2000', no gain, shot at 1675', came free, pulled to 1550', pumped 75 sacks, pulled to 800', pumped 35 sacks, pulled to 20', pumped 60 sacks.


Name of Plugging Contractor: Funk, David A. DBA Oil & Operating Services
Quality Well Service, Inc. License #: 31925 32528
 Address: 190 US Highway 56, Ellinwood, KS 67526

Name of Party Responsible for Plugging Fees: Trans Pacific Oil Corporation
 State of Kansas County, Sedgwick, ss.

Alan Banta (Employee of Operator) or (Operator) on above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

(Signature) [Signature]
 (Address) 100 S. Main, #200, Wichita, KS 67205

SUBSCRIBED and SWORN TO before me this 10th day of August 2007
Glenna E. Lowe My Commission Expires: _____
 Notary Public



Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202

PST

Quality Well Service, Inc.

190 US Highway 56
Ellinwood, KS 67526

Invoice

Date	Invoice #
8/2/2007	887

Bill To
Trans Pacific Oil Corporation 100 S Main, Ste 200 Wichita, KS 67202

RECEIVED
KANSAS CORPORATION COMMISSION
AUG 13 2007
CONSERVATION DIVISION
WICHITA, KS

P.O. No.	Terms	Lease Name
	net	Hermes 1

Description	Qty	Rate	Amount
Rig Time	25	175.00	4,375.00T
Floor Rental		125.00	125.00T
Sand		35.00	35.00T
Cement	4	9.00	36.00T
Shots		160.00	160.00T
Torch		50.00	50.00T
Water Truck	6	75.00	450.00T
Backhoe	3	75.00	225.00T
Phone Calls		15.00	15.00T
Clerical		20.00	20.00T
Wiping Rubber		20.00	20.00T
7-25-07 Drove up, rigged up, checked hole, dug cellar, tore head down, set floor, pulled slips, checked hole, sand at 3200', bailed 4 sacks, ripped pipe, 2400' left over.			
7-26-07 Worked pipe, no gain, ripped 2100', no gain, Perf-Tech shot 2000', no gain, shot 1675', came free, pulled to 1550', pumped 75 sacks, pulled to 800', pumped 35 sacks, pulled to 20', pumped 60 sacks, tore down, loaded out, filled cellar in.			

Subtotal	\$5,511.00
Sales Tax (6.55%)	\$360.97
Total	\$5,871.97