

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-115-21359-00-00
Spot: E2NWNE Sec/Twnshp/Rge: 21-19S-1E
4672 feet from S Section Line, 1682 feet from E Section Line
Lease Name: KLASSEN B Well #: 1
County: MARION Total Vertical Depth: 2882 feet

Operator License No.: 5120
Op Name: RANGE OIL COMPANY, INC.
Address: 125 N MARKET ST STE 1120
WICHITA, KS 67202

| String | Size | Depth (ft) | Pulled (ft) | Comment |
|--------|-------|------------|-------------|-----------------------------|
| PROD | 4.5 | 2880 | | 185 SX CMT. |
| SURF | 8.625 | 293 | | 160 SX CMT. \$ 93.67 |

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 08/07/2007 10:30 AM
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.
Proposal Rcvd. from: RICHARD MCINTYRE Company: QUALITY WELL SERVICE Phone: (620) 727-3410

Proposed Plugging Method: SAND TO 2800' AND CAP WITH 4 SXS CEMENT. PULL PIPE TO 350' AND PUMP CEMENT TO CIRCULATE TO SURFACE.

Plugging Proposal Received By: MICHAEL WILSON WitnessType: PARTIAL
Date/Time Plugging Completed: 08/07/2007 12:30 PM KCC Agent: GREG EVES

Actual Plugging Report:

SAND TO 2800' AND CAPPED WITH 4 SXS OF CEMENT. PULLED PIPE TO 350' AND PUMPED 125 SXS OF CEMENT TO CIRCULATE TO SURFACE. (1630' OF CASING WAS RECOVERED)

Perfs:

| Top | Bot | Thru | Comments |
|------|------|------|----------|
| 2860 | 2864 | | |

INVOICED
DATE 8/20/07
INV. NO. 2008060287

Remarks: UNITED CEMENTING, TICKET #7951, TOTAL = 125 SXS 60/40 POZ 4% GEL

Plugged through: CSG

District: 02

Signed Meg Eves

(TECHNICIAN)

RECEIVED
KANSAS CORPORATION COMMISSION
Form CP-2/3

AUG 16 2007

CONSERVATION DIVISION
WICHITA, KS

Handwritten initials