

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-051-23818-00-01
Spot: W2NENENE Sec/Twnshp/Rge: 8-14S-16W
4950 feet from S Section Line, 380 feet from E Section Line
Lease Name: SCHULTE A Well #: 1
County: ELLIS Total Vertical Depth: 3440 feet

Operator License No.: 9394
Op Name: D-OIL, INC.
Address: 402 MAIN PO BOX 259
VICTORIA, KS 67671

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	5.5	3440	0	150 SX CMT.
SURF	8.625	207	0	140 SX CMT. \$ 111.80

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 08/08/2007 9:00 AM
Plug Co. License No.: 99996 Plug Co. Name: ALLIED CEMENT COMPANY
Proposal Rcvd. from: MIKE DREILING Company: D-OIL, INC. Phone: (785) 735-9225

Proposed: Ordered 275 sxs 60/40 pozmix - 10% gel - 600# hulls.
Plugging: Low fluid level. Operator did OWWO - decided it was non commercial - replugged.
Method: Well was first plugged 12/01/1998.

Plugging Proposal Received By: HERB DEINES WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 08/08/2007 10:00 AM KCC Agent: BRUCE RODIE

Actual Plugging Report:

Tied onto casing - started mixing hulls - pumped 260 sxs cement down casing with 600# hulls.
Max. P.S.I. 700#. S.I.P. 700#.
Backside was filled to surface.

Perfs:

Top	Bot	Thru	Comments
3126	3129		
3058	3074		

INVOICED
DATE 8-16-07
INV. NO. 2008060265

RECEIVED
KANSAS CORPORATION COMMISSION

AUG 13 2007

CONSERVATION DIVISION
WICHITA, KS

Remarks: ALLIED CEMENTING COMPANY-TICKET #33312.

Plugged through: CSG

District: 04

Signed

Bruce Rodie

(TECHNICIAN)

AUG 08 2007

PRG

replacement card

GROSSCO INC
VICTORIA KS 67671

8-14S-16W
50'W, C NENE NE

1 SCHULTE TWIN, AMOS

site: 1-1/4 E OF VICTORIA KS
cont: DREILING OIL

dy: ELLIS
field: VICTORIA NORTH

API 15-051-23818

card:
if date 02/29/84 opd date 03/13/84 drig comp 03/18/84 card issued 01/31/85 last revised 09/21/98

ELV: 1900 KB, 1895 GL
1 cps depth/ datum
RTD 3440 - 1540
NO TOPS RPTD

IP status:
OIL, P 13 BO & 45 BWPD, LKC 3176-3415 OA, 01/25/85
INFO REL: 9/21/98 - ADDED ELEV & COMP INFO
NOTE: INFO REL 1/20/97 - WAS TEMP COMP
CSG: 8-5/8" 207 / 140 SX, 5-1/2" 3439 / 150 SX
SHOWS: 3194-3197 (LM, SFO, PORO), 3230-3236 (LM, CHTY, SFO), 3310-3320 (LM, SPTD STN)
NO CORES OR DSTS
MICT - CO, PF (LKC) 3176-3180, 3222-3224, 3242-3252, 3334-3338, 3386-3391, 3405-3415, AC'D, SO, POP, P 13 BO & 45 BWPD, 1/25/85; UPDATE: DWI PROD HISTORY CUM P 2091 BO TOTAL FROM 8/89 THRU 2/94, LAST PROD P 101 BO (2/94); NO OTHER INFO AVAILABLE

COPYRIGHT 1998
INDEPENDENT OIL & GAS SERVICE, INC.
WICHITA, KANSAS

15