

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-159-22544-00-00  
Spot: NESWSE Sec/Twnshp/Rge: 24-20S-9W  
930 feet from S Section Line, 1360 feet from E Section Line  
Lease Name: TIP Well #: 1  
County: RICE Total Vertical Depth: 3567 feet

Operator License No.: 32924

String	Size	Depth (ft)	Pulled (ft)	Comment
SURF	8.625	371	0	

Op Name: GILBERT-STEWART OPERATING LLC

Address: 1801 BROADWAY - SUITE 450  
DENVER, CO 80202

\$115.93

Well Type: OK DH

KCC Per Per GRB  
UIC Docket No: 8/15/07

Date/Time to Plug: 07/31/2007 6:00 PM

Plug Co. License No.: 33350

Plug Co. Name: SOUTHWIND DRILLING, INC.

Proposal Rcvd. from: LOU TRESNER

Company: SOUTHWIND DRILLING, INC.

Phone: (620) 564-3800

Proposed Plugging Method: Fill hole with heavy mud & spot cement through drill pipe. Spot 35 sxs. cement @ top of Arbuckle, 35 sxs. cement @ 1,100', 35 sxs. cement @ 700', 35sxs. cement 50' below surface pipe, 25 sxs. cement @ 60', 15 sxs. cement in rat hole, & 10 sxs. cement in mouse hole.

Plugging Proposal Received By: DUANE KRUEGER

Witness Type: NONE

Date/Time Plugging Completed: 07/31/2007 9:30 PM

KCC Agent: MICHAEL WILSON

Actual Plugging Report:

Perfs:

Filled hole with heavy mud & spotted cement through drill pipe. Spotted 35 sxs. cement @ 3,515', 35 sxs. cement 1,100', 35 sxs. cement @ 700', 35 sxs. cement @ 425', 25 sxs. cement @ 60', 15 sxs. cement in rat hole, & 10 sxs. cement in mouse hole.

**INVOICED**

DATE 8-16-07

INV. NO. 2008060268

RECEIVED  
KANSAS CORPORATION COMMISSION

**AUG 09 2007**

CONSERVATION DIVISION  
WICHITA, KS

Remarks: USED 60/40 POSMIX W/4% GEL BY BASIC ENERGY. INVOICE #16405.

Plugged through: DP

District: 02

Signed Michael Wilson

(TECHNICIAN)

*Perf*