

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-167-08573-00-01
Spot: SESESE Sec/Twnshp/Rge: 15-15S-13W
330 feet from S Section Line, 330 feet from E Section Line
Lease Name: COBB Well #: 1
County: RUSSELL Total Vertical Depth: 3315 feet

Operator License No.: 33525
Op Name: MID AMERICA PRODUCTION MANAG
Address: 250 N. KANSAS
WICHITA, KS 67214

String	Size	Depth (ft)	Pulled (ft)	Comment
SURF	8	276	0	w/unknown sxs cmt

\$ 107.74

Well Type: SWD UIC Docket No: _____ Date/Time to Plug: 08/07/2007 10:00 AM
Plug Co. License No.: 32528 Plug Co. Name: FUNK, DAVID A. DBA OIL AND OPERATING SERVICES
Proposal Rcvd. from: BILL TATRO Company: MID AMERICA PRODUCTION MAN Phone: (785) 483-5957

Proposed Plugging Method: Ordered 110 sxs 60/40 pozmix - 10% gel.
Old D&A to be drilled down to 1600' and re-plugged.
Re-plugged for injection permit.

Plugging Proposal Received By: HERB DEINES WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 08/07/2007 11:30 AM KCC Agent: BRUCE RODIE

Actual Plugging Report:

Drilled out to 1600'.
Ran tubing to 1559' - tied to tubing - pumped 25 sxs cement.
Pulled tubing to 839' - tied to tubing - pumped 25 sxs cement.
Pulled tubing to 329' - tied to tubing - pumped 40 sxs cement.
Pulled tubing to 59' - circulated to surface with 20 sxs cement.
Pulled tubing - topped off.

Perfs:

INVOICED
DATE 8/16/07
INV. NO. 2008060270

Remarks: QUALITY OILWELL CEMENTING-TICKET #1410.

Plugged through: TBG

District: 04

Signed Bruce Rodie
(TECHNICIAN)

AUG 07 2007

RECEIVED
KANSAS CORPORATION COMMISSION
Form CP-2/3
AUG 09 2007
CONSERVATION DIVISION
WICHITA, KS

E. H. ADAIR

#1

COBB

15-15-13W
SE SE SE

Contr.

RUSSELL

County

E 1810 Comm

Comp 10-7-49

IP D & A

Tops	Depth	Datum
LMS	304	
CONG	3309	
ARB	3312	
T.D.	3315	

8" - 276

INDEPENDENT OIL & GAS SERVICE
WICHITA, KANSAS

RECEIVED

JAN 24 2007

KCC WICHITA