

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-053-21151-00-00
Spot: SENESE Sec/Twnshp/Rge: 27-17S-9W
1650 feet from S Section Line, 430 feet from E Section Line
Lease Name: MOLLHAGEN Well #: 7
County: ELLSWORTH Total Vertical Depth: 3250 feet

Operator License No.: 32325
Op Name: POPP OPERATING, INC.
Address: 191 NE 150 RD. PO BOX 187
HOISINGTON, KS 67544

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	5.5	3247		100 SX CMT
SURF	8.625	512		250 SX CMT

\$ 105.63

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 08/01/2007 1:30 PM
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.
Proposal Rcvd. from: RICHARD MCINTYRE Company: QUALITY WELL SERVICE Phone: (620) 727-3409

Proposed Plugging Method: SEE BELOW

Plugging Proposal Received By: MICHAEL WILSON Witness Type: PARTIAL
Date/Time Plugging Completed: 08/01/2007 4:30 PM KCC Agent: VIRGIL CLOTHIER

Actual Plugging Report:

SAND PERFS TO 3100' & CAP WITH 5 SX'S CEMENT, CUT OFF CASING @ 2470' & PULL TO 1175' AND PUMP 35 SX'S CEMENT, PULL CASING TO 800' & PUMP 35 SX'S CEMENT, PULL CASING TO 560' & CIRCULATE CEMENT TO SURFACE. USED 100 LBS COTTON SEED HULLS @ 1175' TO 800'.

Perfs:

Top	Bot	Thru	Comments
3160	3161		
3154	3155		

INVOICED
DATE 8/20/07
INV. NO. 2008060286

Remarks: 60-40 POZ, 4% GEL. QUALITY CEMENT TICKET #1570.

Plugged through: CSG

District: 02

Signed

Virgil Clothier

(TECHNICIAN)

RECEIVED
KANSAS CORPORATION COMMISSION Form CP-2/3

AUG 16 2007

CONSERVATION DIVISION
WICHITA, KS

Per