

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-185-30190-00-00
Spot: NESESE Sec/Twnshp/Rge: 20-21S-12W
990 feet from S Section Line, 330 feet from E Section Line
Lease Name: MUELLER B Well #: 2
County: STAFFORD Total Vertical Depth: 3637 feet

Operator License No.: 5614
Op Name: HUTCHINSON, WILLIAM S. DBA HUTC
Address: PO BOX 521
DERBY, KS 67037

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	5.5	3586	2225	WITH 100 SX CMT
SURF	8.625	269		WITH 250 SX CMT

\$ 118.20

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 08/09/2007 4:30 PM
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.
Proposal Rcvd. from: MIKE KELSO Company: MIKE'S TESTING & SALVAGE, INC Phone: (620) 938-2537

Proposed Plugging Method: SAND TO 3587' & 5 SX CMT. PLUG AT 700' WITH 10 SX GEL & 50 SX CMT. PLUG AT 300' WITH 50 SX CMT. PLUG AT 40' WITH 15 SX CMT.

Plugging Proposal Received By: RICHARD LACEY WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 08/09/2007 6:01 PM KCC Agent: RICHARD LACEY

Actual Plugging Report:

SANDED TO 3587' & 5 SX CMT WITH DUMP BAILER. SPOTTED PLUGS THROUGH CASING WHILE PULLING. 1ST PLUG AT 700' WITH 9 SX GEL & 50 SX CMT. 2ND PLUG AT 300' WITH 50 SX CMT. 3RD PLUG AT 40' WITH 15 SX CMT.

Perfs:

Top	Bot	Thru	Comments
3586	3637	OH	


INVOICED

DATE 8/22/07
INV. NO. 2008060297

Remarks: USED 60/40 POZMIX 6% GEL BY COPELAND ACID.

Plugged through: CSG

District: 01



Signed

Richard W. Lacey

(TECHNICIAN)

RECEIVED
KANSAS CORPORATION COMMISSION
Form CP-2/3

AUG 20 2007

CONSERVATION DIVISION
WICHITA, KS