

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-065-23326-00-00  
Spot: NENWSE Sec/Twnshp/Rge: 27-10S-22W  
2300 feet from S Section Line, 1670 feet from E Section Line  
Lease Name: FAULKNER Well #: 1-27  
County: GRAHAM Total Vertical Depth: 4050 feet

Operator License No.: 4058  
Op Name: AMERICAN WARRIOR, INC.  
Address: PO BOX 399  
GARDEN CITY, KS 67846

String	Size	Depth (ft)	Pulled (ft)	Comment
SURF	8.625	223		

\$131.63

Well Type: DH UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 08/18/2007 8:00 AM  
Plug Co. License No.: 31548 Plug Co. Name: DISCOVERY DRILLING  
Proposal Rcvd. from: TOM ALM Company: DISCOVERY DRILLING Phone: (785) 623-2920

Proposed Plugging Method: Ordered 225 sxs 60/40 pozmix - 6% gel with 1/4# flocele per sack.  
Space all plugs with heavy drilling mud through drill pipe.

Plugging Proposal Received By: BRUCE BASYE WitnessType: NONE  
Date/Time Plugging Completed: 08/18/2007 9:45 AM KCC Agent: BRUCE BASYE

Actual Plugging Report:

1st. Plug at 3975' w/25 sxs.  
2nd. Plug at 1840' w/25 sxs.  
3rd. Plug at 1000' w/100 sxs.  
4th. Plug at 275' w/40 sxs.  
5th. Plug at 40' w/10 sxs.  
Rathole with 15 sxs.  
Mousehole with 10 sxs.

Perfs:

INVOICED  
DATE 8/22/07  
INV. NO. 2008060305

RECEIVED  
KANSAS CORPORATION COMMISSION  
AUG 22 2007  
CONSERVATION DIVISION  
WICHITA, KS

Remarks: ALLIED CEMENTING COMPANY.

Plugged through: DP

District: 04

HO

Signed

Bruce Basye  
(TECHNICIAN)

Form CP-2/3

AUG 21 2007

PT