

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-011-22922-00-00
Spot: SWNENWNW Sec/Twnshp/Rge: 26-26S-22E
440 feet from N Section Line, 820 feet from W Section Line
Lease Name: MCVAY Well #: 1-26
County: BOURBON Total Vertical Depth: 680 feet

Operator License No.: 33564
Op Name: COALBED TECHNOLOGY, LLC
Address: 401 S. BOSTON AVE., SUITE 3000
TULSA, OK 74103

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	4.5	661	0	98 SX
SURF	8.625	24	0	4 SX

\$ 35.00

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 08/07/2007 5:00 PM
Plug Co. License No.: 33798 Plug Co. Name: WILLIS WELL SERVICES, INC.
Proposal Rcvd. from: ED WILLIS Company: _____ Phone: (620) 431-8583

Proposed Plugging Method: PULL TUBING. TEI ON TO 4 1/2". BULLHEAD 56 FT. CMT. DOWN 4 1/2. CUT OFF 4 1/2 & 8 5/8. RESTORE LOCATION.

Plugging Proposal Received By: CLAYTON TITEL Witness Type: NONE
Date/Time Plugging Completed: 08/08/2007 12:00 PM KCC Agent: CLAYTON TITEL

Actual Plugging Report:

THE PUMP TRUCK WAS CONNECTED DIRECTLY TO THE 4 1/2" CASING. COTTON SEED HULL WERE MIXED WITH THE FIRST OF THE CEMENT TO BE PUMPED. 1 1/2 BAGS OF COTTON SEED HULLS AND 182 SACKS OF CEMENT WERE PUMPED INTO THIS WELL. ON 07/08/07 1" PIPE WAS USED TO TAG THE SET CEMENT AT 275'. CEMENT WAS PUMPED INTO THE 1" PIPE UNTIL CEMENT CIRCULATED FROM THE CASING AT SURFACE. THE 1" WAS REMOVED. DISPLACEMENT WAS FILLED FROM SURFACE. 210 SACKS OF CEMENT TOTAL WERE PUMPED INTO THIS WELL.

RECEIVED
KCC DISTRICT #3

AUG 15 2007 CPT

CHANUTE, KS

Perfs:

Top	Bot	Thru	Comments
610	614		
228	243		

INVOICED

DATE 8/22/07
INV. NO. 2008060295

Remarks:

Plugged through: CSG

District: 03

Signed Clayton P. Titel
(TECHNICIAN)

RECEIVED
KANSAS CORPORATION COMMISSION Form CP-2/3

AUG 20 2007

CONSERVATION DIVISION
WICHITA, KS

PFT