

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-011-22923-00-00
Spot: SWSWSW Sec/Twnshp/Rge: 25-25S-21E
330 feet from S Section Line, 330 feet from W Section Line
Lease Name: GUDER Well #: 1-25
County: BOURBON Total Vertical Depth: 942 feet

Operator License No.: 33564
Op Name: COALBED TECHNOLOGY, LLC
Address: 401 S. BOSTON AVE., SUITE 3000
TULSA, OK 74103

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	4.5	922	0	138 sx
SURF	8.625	22	0	4 SX

\$ 35.00

Well Type: CM UIC Docket No: _____ Date/Time to Plug: 08/07/2007 12:30 PM
Plug Co. License No.: 33798 Plug Co. Name: WILLIS WELL SERVICES, INC.
Proposal Rcvd. from: ED WILLIS Company: _____ Phone: (620) 431-8583

Proposed Plugging Method: PULL TUBING. TEI ON TO 4 1/2". BULLHEAD 44 FT. CMT. DOWN 4 1/2. CUT OFF 4 1/2 & 8 5/8. RESTORE LOCATION.

Plugging Proposal Received By: CLAYTON TITEL WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 08/07/2007 2:00 PM KCC Agent: CLAYTON TITEL

Actual Plugging Report:

THE PUMP TRUCK WAS CONNECTED DIRECTLY TO THE 4 1/2" CASING. COTTON SEED HULLS WERE MIXED WITH THE FIRST OF THE CEMENT TO BE PUMPED. CEMENT WAS PUMPED INTO THE 4 1/2" CASING UNTIL THE WELL WOULD HOLD PRESSURE. THE WELL WAS THEN SHUT IN AT 300 P.S.I..64 SACKS OF CEMENT WERE PUMPED INTO THIS WELL.

Perfs:

Top	Bot	Thru	Comments
584	685		

RECEIVED
KCC DISTRICT #3

AUG 15 2007 CPT

CHANUTE, KS

INVOICED

DATE 8/22/07
INV. NO. 2008060295

Remarks: WELL WAS GPS'ED ON 08/07/07 AS GUD 1-25 AT 095.05995 N & 37.83526 W..

Plugged through: CSG

District: 03

Signed Clayton P. Titel
(TECHNICIAN)

RECEIVED Form CP-2/3
KANSAS CORPORATION COMMISSION

AUG 20 2007

CONSERVATION DIVISION
WICHITA, KS

PPT