

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-011-22925-00-00  
Spot: S2SESW Sec/Twnshp/Rge: 29-25S-22E  
330 feet from S Section Line, 1950 feet from W Section Line  
Lease Name: F LORD Well #: 1-29  
County: BOURBON Total Vertical Depth: 734 feet

Operator License No.: 33564  
Op Name: COALBED TECHNOLOGY, LLC  
Address: 401 S. BOSTON AVE., SUITE 3000  
TULSA, OK 74103

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	4.5	721	0	106 sx
SURF	8.625	23	0	4 sx

*\$ 35.00*

Well Type: CM UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 08/07/2007 2:00 PM  
Plug Co. License No.: 33798 Plug Co. Name: WILLIS WELL SERVICES, INC.  
Proposal Rcvd. from: ED WILLIS Company: \_\_\_\_\_ Phone: (620) 431-8583

Proposed Plugging Method: PULL TUBING. TIE ON TO 4 1/2". BULLHEAD 47 FT CMT DOWN 4 1/2. CUTT OFF 4 1/2 & 8 5/8. RESTORE LOCATION.

Plugging Proposal Received By: CLAYTON TITEL WitnessType: COMPLETE (100%)  
Date/Time Plugging Completed: 08/07/2007 3:00 PM KCC Agent: CLAYTON TITEL

**Actual Plugging Report:**

THE PUMP TRUCK WAS CONNECTED DIRECTLY TO THE 4 1/2" CASING. COTTON SEED HULLS WERE MIXED WITH THE FIRST OF THE CEMENT TO BE PUMPED. CEMENT WAS PUMPED INTO THE 4 1/2" CASING UNTIL THE WELL WOULD HOLD PRESSURE. THE WELL WAS THEN SHUT IN AT 400 P.S.I.. 55 SACKS OF CEMENT WERE PUMPED INTO THIS WELL.

RECEIVED  
KCC DISTRICT #3  
AUG 15 2007 CPT  
CHANUTE, KS

**Perfs:**

Top	Bot	Thru	Comments
672	675		

**INVOICED**  
DATE 8-22-07  
INV. NO. 2008060295

Remarks: THIS WELL WAS GPS'D AS LOR 1-29 AT 095.01691 W. & 37.83520 N..

Plugged through: CSG

District: 03

Signed Clayton P. Titel  
(TECHNICIAN)

RECEIVED  
KANSAS CORPORATION COMMISSION Form CP-2/3

**AUG 20 2007**

CONSERVATION DIVISION  
WICHITA, KS

*PPT*