

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION OIL & GAS CONSERVATION DIVISION WELL PLUGGING RECORD K.A.R. 82-3-117

Form CP-4 December 2003 Type or Print on this Form Form must be Signed All blanks must be Filled

Lease Operator: Berexco, Inc. Address: PO Box 723 Hays, KS 67601 Phone: (785) 628-6101 Operator License #: 5363 Type of Well: OIL Docket #: The plugging proposal was approved on: 8-1-07 by: Pat Bedore Is ACO-1 filed? Producing Formation(s): L-KC E, L-KC F

API Number: 15-065-21039-00-00 Lease Name: Worcester Well Number: 1-21 Spot Location (QQQQ): SE - NW 3300 Feet from North / South Section Line 3300 Feet from East / West Section Line Sec. 21 Twp. 7 S. R. 22 County: Graham Date Well Completed: 7-18-78 Plugging Commenced: 8-1-07 Plugging Completed: 8-2-07

Show depth and thickness of all water, oil and gas formations.

Table with 7 columns: Formation, Content, From, To, Size, Put In, Pulled Out. Rows include L-KC OIL formations with depths and casing sizes.

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole.

RIG UP PERF TECH PERF @ 2475' 2 HOLES 1975 2 HOLES & 1175 2 HOLES PER HERB DIENES. TIH W/ TBG TO 3650' MIX 60 SKS 60/40 10% GEL W/ 300# HULLS PULL TBG TO 2400 MIX 60SKS 60/40 W/ 300# HULLS PULL TBG TO 1200 MIX 45 SKS 60/40 10% GEL W/ 200# HULLS CIRCULATED CEMENT TOH W/ TBG. FILL CSG W/ 15 SKS PUMP 120 SKS 60/40 10% GEL DOWN 8-5/8, ANN IS FULL,

RECEIVED KANSAS CORPORATION COMMISSION


AUG 21 2007

CONSERVATION DIVISION WICHITA, KS

Name of Plugging Contractor: Berexco, Inc. License #: 5363 Address: PO Box 723 Hays, KS 67601 Name of Party Responsible for Plugging Fees: Mark Leiker w/ Berexco, Inc. State of KS County, ELLIS, ss.

(Employee of Operator) or (Operator) on above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

(Signature) Mark Leiker (Address) PO Box 723 Hays, KS 67601



SUBSCRIBED and SWORN TO before me this 14 day of August, 20 07 Shanna Miller Notary Public My Commission Expires: 9/19/09

Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202

Handwritten initials/signature in the bottom right corner.