

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

**KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING RECORD
K.A.R. 82-3-117**

Form CP-4
December 2003
**Type or Print on this Form
Form must be Signed
All blanks must be Filled**

Lease Operator: VESS OIL CORPORATION
 Address: 1700 Waterfront Parkway, Bldg. 500, Wichita, KS 67206
 Phone: (316) 682-1537 Operator License #: 5030
 Type of Well: oil Docket #: _____
 (Oil, Gas D&A, SWD, ENHR, Water Supply Well, Cathodic, Other) (If SWD or ENHR)
 The plugging proposal was approved on: verbal (Date)
 by: Rich Williams (KCC District Agent's Name)
 Is ACO-1 filed? Yes No If not, is well log attached? Yes No
 Producing Formation(s): List All (If needed attach another sheet)
LKC Depth to Top: 3124 Bottom: 3216 T.D. 3381
Arb Depth to Top: 3341 Bottom: 3351 T.D. 3381
 _____ Depth to Top: _____ Bottom: _____ T.D. _____

API Number: 15 - 051-25,591-00-00
 Lease Name: Dehoff A
 Well Number: 8
 Spot Location (QQQQ): 70'W of 1090 990 - SW - NE - NW *KCC PKT 8/22/07 per CP2/3*
 _____ Feet from North / South Section Line
 1910 Feet from East / West Section Line
 Sec. 30 Twp. 11 S. R. 16 East West
 County: Ellis
 Date Well Completed: 2/9/07
 Plugging Commenced: 7/25/07
 Plugging Completed: 7/25/07

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface Conductor & Production)				
Formation	Content	From	To	Size	Put In	Pulled Out
				8-5/8	1037'	
				5-1/2	3428 3108	<i>per per CP2/3 8/22/07</i>

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

Plugged and Abandoned as follows: MIRU. TIH w/2 7/8" workstring to 3250'. Pump 125 sx 60/40 poz w/10% gel and 500# hulls. Pulled tbg to 1500' and circulated cement to surface w/125 sx same cement. TOH w/tbg. Pumped down 5 1/2" casing w/30 sx - 200#. SIP - 200#. Approved by Rich Williams w/KCC.

Name of Plugging Contractor: Allied Cementing Co., Inc. License #: 99996 **RECEIVED KANSAS CORPORATION COMMISSION**
 Address: P.O. Box 31, Russell, KS 67665-0031 **AUG 16 2007**
 Name of Party Responsible for Plugging Fees: Vess Oil Corporation **CONSERVATION DIVISION WICHITA, KS**
 State of Kansas County, Sedgwick, ss.
Pat Canaday (Employee of Operator) or (Operator) on above-described well, being first duly

sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

(Signature) *[Signature]*
 (Address) 1700 Waterfront Parkway, Bldg. 500, Wichita, KS 67206

SUBSCRIBED and SWORN TO before me this 13th day of August 20 07
[Signature] My Commission Expires: _____
 Notary Public **MICHELLE D. HENNING NOTARY PUBLIC STATE OF KANSAS My Appl. Exp. 7/10/09**

Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202

per

ALLIED CEMENTING CO., INC. 33278

PERMIT TO P.O. BOX 31
RUSSELL, KANSAS 67665

SERVICE POINT:
Russell

DATE <u>2-25-07</u>	SEC. <u>30</u>	TWP. <u>11 S</u>	RANGE <u>16 W</u>	CALLED OUT	ON LOCATION	JOB START	JOB FINISH <u>12:45 p.m.</u>
LEASE <u>Dehoff</u>	WELL # <u>8</u>	LOCATION <u>Cadell River Rd Jct.</u>		COUNTY <u>Ellis</u>	STATE <u>Ks.</u>		
<input checked="" type="radio"/> OLD OR NEW (Circle one)		<u>2E 25 Winto</u>					

CONTRACTOR Smoky Hill Well Service
 TYPE OF JOB Old Hole Plug
 HOLE SIZE _____ T.D. _____
 CASING SIZE 5 1/2 DEPTH _____
 TUBING SIZE 2 7/8 DEPTH 3250
 DRILL PIPE _____ DEPTH _____
 TOOL _____ DEPTH _____
 PRES. MAX _____ MINIMUM _____
 MEAS. LINE _____ SHOE JOINT _____
 CEMENT LEFT IN CSG. _____
 PERFS. _____
 DISPLACEMENT _____

OWNER _____
 CEMENT Used 2800 lbs 200# hulls
 AMOUNT ORDERED 400 60% 10% Gel
200 #hulls

COMMON	<u>168</u>	@	<u>11.10</u>	<u>1864.80</u>
POZMIX	<u>112</u>	@	<u>6.20</u>	<u>694.40</u>
GEL	<u>24</u>	@	<u>16.65</u>	<u>399.60</u>
CHLORIDE		@		
ASC		@		
<u>Hulls</u>	<u>14</u>	@	<u>25.50</u>	<u>357.00</u>
		@		
		@		
		@		
		@		
		@		
		@		
HANDLING	<u>448</u>	@	<u>1.90</u>	<u>851.20</u>
MILEAGE	<u>.09/sk/mile</u>			<u>1451.52</u>
TOTAL				<u>5618.52</u>

EQUIPMENT

PUMP TRUCK CEMENTER Shane
 # 366 HELPER John
 BULK TRUCK
 # 396 DRIVER Chuck
 BULK TRUCK
 # _____ DRIVER _____

REMARKS:

3250' Mixed 125 sks with 500# hulls
Pulled up to 1500' to Circulate Cement
took 125 sks with 200# hulls +
Circulate Cement. Came out
of hole put surge on mixed
30 sks & shut in @ 200 psi.
Back side was Two Staged,

SERVICE

DEPTH OF JOB			
PUMP TRUCK CHARGE			<u>720.00</u>
EXTRA FOOTAGE		@	
MILEAGE	<u>36</u>	@	<u>6.00</u> <u>216.00</u>
MANIFOLD		@	
		@	
		@	
TOTAL <u>936.00</u>			

CHARGE TO: Vess Oil
 STREET _____
 CITY _____ STATE _____ ZIP _____

PLUG & FLOAT EQUIPMENT

	@	
	@	
	@	
	@	
	@	
TOTAL _____		

To Allied Cementing Co., Inc.
 You are hereby requested to rent cementing equipment and furnish cementer and helper to assist owner or contractor to do work as is listed. The above work was done to satisfaction and supervision of owner agent or contractor. I have read & understand the "TERMS AND CONDITIONS" listed on the reverse side.

Thanks!

SIGNATURE _____



TAX _____
 TOTAL CHARGE _____
 DISCOUNT _____ IF PAID IN 30 DAYS

PRINTED NAME _____