

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING RECORD
K.A.R. 82-3-117

Form CP-4
December 2003
Type or Print on this Form
Form must be Signed
All blanks must be Filled

Lease Operator: VESS OIL CORPORATION
Address: 1700 Waterfront Parkway, Bldg. 500, Wichita, KS 67206
Phone: (316) 682-1537 Operator License #: 5030
Type of Well: oil Docket #: _____
(Oil, Gas D&A, SWD, ENHR, Water Supply Well, Cathodic, Other) (If SWD or ENHR)
The plugging proposal was approved on: verbal (Date)
by: Rich Williams (KCC District Agent's Name)
Is ACO-1 filed? Yes No If not, is well log attached? Yes No
Producing Formation(s): List All (If needed attach another sheet)
Toronto Depth to Top: 3315 Bottom: 3320 T.D. 3589
LKC Depth to Top: 3337 Bottom: 3514 T.D. 3589
Arbuckle Depth to Top: 3581 Bottom: 3589 T.D. 3589

API Number: 15-163-01,571-00-00
Lease Name: Widman A
Well Number: #1
Spot Location (QQQQ): _____ - S/2 - NE - SW
1526 Feet from North / South Section Line
1980 Feet from East / West Section Line
Sec. 21 Twp. 9 S. R. 18 East West
County: Rooks
Date Well Completed: 5/27/47
Plugging Commenced: 7/13/07
Plugging Completed: 7/16/07

Show depth and thickness of all water, oil and gas formations.

| Oil, Gas or Water Records | | Casing Record (Surface Conductor & Production) | | | | |
|---------------------------|---------|--|----|-------|--------|------------|
| Formation | Content | From | To | Size | Put In | Pulled Out |
| | | | | 8-5/8 | 1435' | - |
| | | | | 5-1/2 | 3581' | - |
| | | | | | | |
| | | | | | | |

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

TIH w/2 7/8" tbg to 2032'. Spotted 150 sc 60/40 poz w/10% gel and 500# hulls. Pulled tbg to 1500' and spotted 275 sx same cement w/700# hulls. Cement did not circulate. TOH w/tbg.


TIH w/workstring and tagged at 900'. Circ cement to surface w/100 sx. TOH w/tbg. Topped off 5 1/2" csg w/5 sx. Press to 200#. Press 8 5/8" and 5 1/2" annulus to 400#. Approved by Rich Williams w/KCC.

Name of Plugging Contractor: Joel Stull, Allied Cementing, a General Partnership License #: 99996
Address: P.O. Box 307, Natoma, KS 67651
Name of Party Responsible for Plugging Fees: Vess Oil Corporation
State of Kansas County, Sedgwick, ss. Pat Canaday ext 101 (Employee of Operator) or (Operator) on above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

(Signature) [Signature]
(Address) 1700 Waterfront Parkway, Bldg. 500, Wichita, KS 67206

SUBSCRIBED and SWORN TO before me this 14th day of August

Michelle D. Henning My Commission Expires: _____
Notary Public



Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202

PKT

Company Cities Service Oil Co. Well No. 1 Farm Widman
 Location 1526' North and 1980' East of SW Corner Sec. 21 T 9 R. 18W
 Elevation 2169 (2167 (H.)) County Rooks State Kansas
 Drig. Comm. May 4, 1947 Contractor R. W. Rine Drilling Company
 Drig. Comp. May 22, 1947 Acid 1000 gals. 5-29-47
 T. D. 3589½' Initial Prod. Depthograph Potential: 3000 oil, no water, 24 hrs.
(Ind. Cap. 4355 bbls.)

7876 - 3545'

CASING RECORD:

8-5/8" @ 1435' cem. 450 sacks cem.
 5-1/2" @ 3581' cem. 150 sacks cem.

Top Lansing 3322'
 Top Arbuckle 3580'
 Penetration 9½'
 Total Depth 3589½'

FORMATION RECORD:

clay & sand 0-40
 shale & shells 470
 shale, shells & sand 680
 shale & shells 1105
 lime 1120
 red bed & shells 1315
 shale, red bed & iron
 pyrite 1400
 shale 1430
 anhydrite 1435
 red rock 1495
 shale & red rock 1780
 shale & shells 2090
 lime & sand 2160
 shale & shells 2245
 lime & shale 2360
 shale & shells 2515
 lime & shale 2605
 shale & iron 2695
 shale, shells & iron 2760
 shale 2950
 shale & lime 3065
 lime & shale 3140
 shale & lime 3220
 lime 3395
 lime & shale 3455
 shale & lime 3582

Fillup:

100' oil in 1 hr. 5 mins. at 3586
 300' oil in 1 hr. 35 mins. at 3586
 1000' oil in 2 hrs. 40 mins. at 3589½
 1490' oil in 3 hrs. 40 mins.
 2038' oil in 6 hrs. 40 mins.
 2238' oil in 10 hrs. 40 mins.

SYFO: 500' OK
 1500' 10
 2000' 10
 2500' 10
 3000' 10

7-7/8" rotary hole.

3582 Rot. TD = 3582 SLM
 lime 3589½ T. D.

RECEIVED
 KANSAS CORPORATION COMMISSION

AUG 16 2007

CONSERVATION DIVISION
 WICHITA, KS

ALLIED CEMENTING CO., INC.

21939

with 3 pipes

REMIT TO P.O. BOX 31
RUSSELL, KANSAS 67665

SERVICE POINT:

Russell

| | | | | | | | |
|--|---------------|-------------------|---|------------------------|------------------------|-----------------------------|------------------------------|
| DATE <i>7-13-07</i> | SEC <i>21</i> | TWP <i>9</i> | RANGE <i>18</i> | CALLED OUT | ON LOCATION | JOB START <i>1:00 PM</i> | JOB FINISH <i>2:00 PM</i> |
| LEASE <i>WIDMAN</i> | | WELL # <i>A-1</i> | LOCATION <i>Plainville 1w 1/2 W 1/2 N</i> | COUNTY <i>ROCKS</i> | STATE <i>KANSAS</i> | | |
| <input checked="" type="radio"/> OLD OR NEW (Circle one) | | | | | | | |

CONTRACTOR *Smoky Hills Well Service* OWNER

TYPE OF JOB *PLUG ABANDONED well*

| | |
|--------------------------|-------------------|
| HOLE SIZE | T.D. |
| CASING SIZE <i>5 1/2</i> | DEPTH <i>3581</i> |
| TUBING SIZE <i>2 7/8</i> | DEPTH <i>2032</i> |
| DRILL PIPE <i>8</i> | DEPTH <i>1435</i> |
| TOOL | DEPTH |
| PRES. MAX <i>100</i> | MINIMUM |
| MEAS. LINE | SHOE JOINT |
| CEMENT LEFT IN CSG. | |
| PERFS. | |
| DISPLACEMENT | |

CEMENT
AMOUNT ORDERED *425 SK 6% 1026.00*

#Hull's

| | | | |
|---------------|---------------------|----------------|----------------|
| COMMON | <i>255 SK</i> | @ <i>11.10</i> | <i>2830.50</i> |
| POZMIX | <i>170 SK</i> | @ <i>6.20</i> | <i>1054.00</i> |
| GEL | <i>3730 SK</i> | @ <i>16.65</i> | <i>499.50</i> |
| CHLORIDE | | @ | |
| ASC | | @ | |
| <i>Hull's</i> | <i>12 SK</i> | @ <i>25.50</i> | <i>306.00</i> |
| | | @ | |
| | | @ | |
| | | @ | |
| | | @ | |
| | | @ | |
| | | @ | |
| | | @ | |
| | | @ | |
| HANDLING | <i>462 Total SK</i> | @ <i>1.90</i> | <i>877.80</i> |
| MILEAGE | <i>47 Ten Mile</i> | @ <i>.094</i> | <i>1954.26</i> |
| TOTAL | | | <i>7522.06</i> |

EQUIPMENT

| | |
|--------------|-----------------------|
| PUMP TRUCK | CEMENTER <i>Glenn</i> |
| # <i>398</i> | HELPER <i>GARY</i> |
| BULK TRUCK | |
| # <i>396</i> | DRIVER <i>Rocky</i> |
| BULK TRUCK | |
| # | DRIVER |

REMARKS:

Ran 2 7/8 tubing to 2032' & spot 150 SK Cement w/ 500# Hull's. Pulled up to 1500' & spot 275 SK Cement w/ 700# Hull's. Cement failed to circulate, had circulation between 8 5/8 & 5 1/2 and also between 2 7/8 tubing and 5 1/2 csg.

THANK'S

SERVICE

| | |
|-------------------|-----------------------------|
| DEPTH OF JOB | <i>720.00</i> |
| PUMP TRUCK CHARGE | <i>255.00</i> |
| EXTRA FOOTAGE | @ |
| MILEAGE <i>47</i> | @ <i>6.00</i> <i>282.00</i> |
| MANIFOLD | @ |
| | @ |
| | @ |

TOTAL *1002.00*

CHARGE TO: *Vess Oil Co.*

STREET _____

CITY _____ STATE _____ ZIP _____

PLUG & FLOAT EQUIPMENT

| | | |
|--|---|--|
| | @ | |
| | @ | |
| | @ | |
| | @ | |
| | @ | |

TOTAL _____

TAX _____

TOTAL CHARGE _____

DISCOUNT _____ IF PAID IN 30 DAYS

SIGNATURE *[Signature]*

PRINTED NAME

To Allied Cementing Co., Inc.
You are hereby requested to rent cementing equipment and furnish cementer and helper to assist owner or contractor to do work as is listed. The above work was done to satisfaction and supervision of owner agent or contractor. I have read & understand the "TERMS AND CONDITIONS" listed on the reverse side.

ALLIED CEMENTING CO., INC.

33236

TO P.O. BOX 31
RUSSELL, KANSAS 67665

SERVICE POINT:

Russell

| | | | | | | | |
|--|-----------------|---|-----------------|---------------------|-----------------|-----------------------------|------------------------------|
| DATE <u>7/607</u> | SEC. <u>21</u> | TWP. <u>9</u> | RANGE <u>18</u> | CALLED OUT | ON LOCATION | JOB START <u>11:30 a.m.</u> | JOB FINISH <u>11:00 a.m.</u> |
| LEASE <u>Wideman A</u> | WELL # <u>1</u> | LOCATION <u>Plainville 1w 1w 1/2 n w into</u> | | COUNTY <u>Rooks</u> | STATE <u>KS</u> | | |
| <input checked="" type="radio"/> OLD OR NEW (Circle one) | | | | | | | |

CONTRACTOR Smoky Hills

TYPE OF JOB oil hole plug

HOLE SIZE _____ T.D. _____

CASING SIZE 5/2 DEPTH _____

TUBING SIZE 2 1/2" DEPTH _____

DRILL PIPE _____ DEPTH _____

TOOL _____ DEPTH _____

PRES. MAX _____ MINIMUM _____

MEAS. LINE _____ SHOE JOINT _____

CEMENT LEFT IN CSG. _____

PERFS. _____

DISPLACEMENT _____

EQUIPMENT

PUMP TRUCK CEMENTER Craig

409 HELPER Adrian

BULK TRUCK

362 DRIVER Doug

BULK TRUCK

_____ DRIVER _____

REMARKS:

1st plug 900' 100sk Cement Circulated!
Mix 10sk down 5/2. Back side fail. Shut in
100ft. 5/2 swage 300# Shut in.

Thanks

CHARGE TO: U.S.S

STREET _____

CITY _____ STATE _____ ZIP _____

To Allied Cementing Co., Inc.
You are hereby requested to rent cementing equipment and furnish cementer and helper to assist owner or contractor to do work as is listed. The above work was done to satisfaction and supervision of owner agent or contractor. I have read & understand the "TERMS AND CONDITIONS" listed on the reverse side.

SIGNATURE _____



OWNER _____

CEMENT USED 110sk 10 Hulls

AMOUNT ORDERED 425 60% 10% 6c1
1000# Hulls

| | | | | |
|--------------|--------------------|---|------------------|----------------|
| COMMON | <u>66</u> | @ | <u>11.10</u> | <u>732.60</u> |
| POZMIX | <u>44</u> | @ | <u>6.20</u> | <u>272.80</u> |
| GEL | <u>11</u> | @ | <u>16.65</u> | <u>183.15</u> |
| CHLORIDE | | @ | | |
| ASC | | @ | | |
| <u>Hulls</u> | <u>20sk</u> | @ | 11.10 | |
| | | @ | | |
| | | @ | | |
| | | @ | | |
| | | @ | | |
| | | @ | | |
| | | @ | | |
| HANDLING | <u>479sk</u> | @ | <u>1.90</u> | <u>910.10</u> |
| MILEAGE | <u>109/sk/mile</u> | | | <u>1724.40</u> |

TOTAL 3823.05

SERVICE

| | | | | |
|-------------------|-----------|---|---------------|---------------|
| DEPTH OF JOB | | | | |
| PUMP TRUCK CHARGE | | | <u>720.00</u> | |
| EXTRA FOOTAGE | | @ | | |
| MILEAGE | <u>40</u> | @ | <u>6.00</u> | <u>240.00</u> |
| MANIFOLD | | @ | | |
| | | @ | | |
| | | @ | | |

~~960.00~~

~~960.00~~

~~960.00~~

TOTAL 960.00

PLUG & FLOAT EQUIPMENT

| | | | |
|--|---|--|--|
| | @ | | |
| | @ | | |
| | @ | | |
| | @ | | |
| | @ | | |

TOTAL _____

TAX _____

TOTAL CHARGE _____

DISCOUNT _____ IF PAID IN 30 DAYS

PRINTED NAME _____