

AUG 17 2007

Form CP-4
December 2003

CONSERVATION DIVISION
WICHITA, KS
Type or Print on this Form
Form must be Signed
All blanks must be Filled

Notice: Fill out COMPLETELY
and return to Conservation Division
at the address below within
60 days from plugging date.

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING RECORD
K.A.R. 82-3-117

Lease Operator: Popp Operating, Inc.
Address: PO BOX 187 HOISINGTON, KS 67544
Phone: (620) 786 - 5514 Operator License #: 32325
Type of Well: OIL Docket #: _____
(Oil, Gas D&A, SWD, ENHR, Water Supply Well, Cathodic, Other) *(If SWD or ENHR)*
The plugging proposal was approved on: 7/07 (Date)
by: DOUG LOUIS (KCC District Agent's Name)
Is ACO-1 filed? Yes No If not, is well log attached? Yes No
Producing Formation(s): List All (If needed attach another sheet)
ARBUCKLE Depth to Top: 3153' Bottom: 3154' T.D. 3205'
ARBUCKLE Depth to Top: 3160' Bottom: 3161' T.D. 3205'

Depth to Top: _____ Bottom: _____ T.D. _____

API Number: 15 - 053-21151-0000
Lease Name: MOLLHAGEN
Well Number: 7
Spot Location (QQQQ): 100' W - SE - NE - SE
1650 Feet from North / South Section Line
430 Feet from East / West Section Line
Sec. 27 Twp. 17 S. R. 9 East West
County: Ellsworth
Date Well Completed: 9/16/05
Plugging Commenced: 7/27/07
Plugging Completed: 8/1/07

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface Conductor & Production)				
Formation	Content	From	To	Size	Put In	Pulled Out
		SURFACE	512'	8-5/8"	512'	NONE
		SURFACE	3247'	5-1/2"	3247'	2470'

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

SAND @ 3100', BAILED 5 SX CEMENT, PULLED SLIPS, RIPPED PIPE @ 2470'. PULLED CSG TO 1175', PUMPED 35 SX, PULLED CSG TO 800', PUMPED 35 SX CEMENT, PULLED CSG 560', CIRCULATED CEMENT TO SURFACE W/ 140 SX CEMENT. ALL CEMENT 60/40 POZ 4% GEL W/ 300# HULLS.


Name of Plugging Contractor: QUALITY OILWELL CEMENTING, INC License #: 31925
Address: 190 US HWY 56 ELLINWOOD, KS 67526

Name of Party Responsible for Plugging Fees: POPP OPERATING, INC.
State of KANSAS County, BARTON, ss.

RICKEY POPP (Employee of Operator) or (Operator) on above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well as filed, and the same are true and correct, so help me God.

(Signature) Rickey Popp
(Address) PO BOX 187 HOISINGTON, KS 67544

SUBSCRIBED and SWORN TO before me this 14th day of August, 2007
Jane M. Steinert My Commission Expires: 5/20/11
Notary Public



PKY

