

15-163-00800-00-00


STATE OF KANSAS
STATE CORPORATION COMMISSION

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 North Market, Insurance Bldg.
Wichita, Kansas

WELL PLUGGING RECORD

Rooks County. Sec. 23 Twp. 9 Rge. (E) 19 (W)
Location as "NE/CNW/SW" or footage from lines SW NE SW/4
Lease Owner Herman Geo. Kaiser, Oil Producer
Lease Name Saindon Well No. 1
Office Address 909 Palace Building, Tulsa, Oklahoma
Character of Well (completed as Oil, Gas or Dry Hole) D & A
Date well completed August 6, 19 60
Application for plugging filed August 6, 19 60
Application for plugging approved August 6, 19 60
Plugging commenced August 6, 19 60
Plugging completed August 6, 19 60
Reason for abandonment of well or producing formation Dry

NORTH



Locate well correctly on above
Section Plat

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Eldon Petty
Producing formation Depth to top Bottom Total Depth of Well 3546 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8	211	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

MUDDED HOLE WITH HEAVY ROTARY MUD TO 500 FEET, SET PLUG AND
CEMENTED WITH 20 SACKS CEMENT. MUDDED HOLE TO 200 FEET.
SET PLUG AND CEMENTED WITH 20 SACKS CEMENT. MUDDED TO 40
FEET. SET PLUG AND CEMENTED WITH 10 SACKS CEMENT AND 1/2 SACK HULLS.

RECEIVED
STATE CORPORATION COMMISSION
8/12/60
AUG 12 1960
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor H-30, Inc.
Address 909 Palace Building, Tulsa, Oklahoma

STATE OF Kansas, COUNTY OF Sedgwick
L. C. Sponenberg employee or contractor
(employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) L. C. Sponenberg

(Address)

SUBSCRIBED AND SWORN TO before me this 10th day of August, 19 60

My commission expires February 13, 1964

Rose Furey
Rose Furey Notary Public.



15-163-00800-00-0

KANSAS GEOLOGICAL SOCIETY
KANSAS WELL LOG BUREAU - KANSAS WELL SAMPLE BUREAU
KANSAS GEOLOGICAL SOCIETY BUILDING
508 EAST MURDOCK - WICHITA, KANSAS

COMPANY **Herman Geo. Kaiser**

SEC. **23** T. **9** R. **19**
LOC. **SW NE SW/4**

FARM **Saindon** NO. **1**

COUNTY **Rooke**

TOTAL DEPTH **3546'**


COMM. **7/28/60**

COMP. **8/6/60**

SHOT OR TREATED

CONTRACTOR **H-30, Inc.**

ISSUED



CASING

20 10
15 8 **211'**
12 6
13 5

2108 K.B.
ELEVATION **2105 D.F.**

PRODUCTION **D & A**

FIGURES INDICATE BOTTOM OF FORMATIONS

Sand	20'
Shale, Shells with Sand Stks.	212'
Shale & Shells	610'
Sand	670'
Shale	790'
Sand	895'
Shale	920'
Hard sand & pyrite	1190'
Shale & shells	1475'
Anhydrite	1514'
Shale, Shells & Red Bed	1620'
Shale	1900'
Lime with Shale Stks.	1985'
Lime & Shale	2255'
Lime	2375'
Shale & Lime	3275'
Kansas City Lime	3330'
Lime	3368'
Lime with Shale Breaks	3411'
Kansas City Lime	3466'
Lime & Shale	3531'
Arbuckle	3546'

8/12/60
CONSERVATION DEPARTMENT
Wichita, Kansas

Formation Tops:

	<u>Sample</u>	<u>Electric</u>
Topeka		3039 - 931
Heebner	3244 - 1136	3244 - 1136
Toronto		3264 - 1156
Kansas City	3285 - 1177	3285 - 1177
Arbuckle	3522 - 1414	3524 - 1416

I hereby certify that this is a true and correct log of the above described well as shown by the drilling reports.

H-30, INC.

By *I. C. Spensberg*
I. C. Spensberg

STATE OF KANSAS)
) SS.
COUNTY OF SEDGWICK)

Subscribed and sworn to before me, a Notary Public, in and for said County and State this 10th day of August, 1960.

Rose Furey
Rose Furey, Notary Public

My Commission expires February 13, 1964