

15-163-01674-00-00

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
200 Colorado Derby Building  
Wichita, Kansas 67202

WELL PLUGGING RECORD  
K.A.R.-82-3-117

API NUMBER None

LEASE NAME CERROW

WELL NUMBER 5

3630 Ft. from S Section Line

4290 Ft. from E Section Line

SEC. 23 TWP. 9S RGE. 19 ~~XX~~ (W)

COUNTY Rooks

Date Well Completed 3/18/55

Plugging Commenced 1/28/86

Plugging Completed 1/28/86

LEASE OPERATOR Kaiser-Francis Oil Company

ADDRESS P. O. Box 21468, Tulsa, OK 74121-1468

PHONE#(918) 494-0000 OPERATORS LICENSE NO. 6568

Character of Well Oil

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? Yes

Which KCC/KDHE Joint Office did you notify? District 6, Hays, KS

Is ACO-1 filed? on old form if not, is well log attached? ---

Producing Formation Arbuckle Depth to Top 3522 Bottom 3530 T.D. 3530

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
Arbuckle	Oil	3522	30	8-5/8	205	-0-
				5-1/2	3523	-0-

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set. Spotted 1st plug @ 2015' w/100 SXS 60/40 poz + 1-1/2 SXS hulls. Spotted 2nd plug @ 1000' & circulated to Surf w/110 SXS cement + 1-1/2 SXS hulls. Pump 40 SXS down annulus.

JOB COMPLETE

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Kaiser-Francis Oil Company License No. 6568

Address P. O. Box 21468, Tulsa, OK 74121-1468

STATE OF Oklahoma COUNTY OF Tulsa, ss.

Charlotte Van Valkenburg (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) C. Van Valkenburg

(Address) P. O. Box 21468, Tulsa, OK 74121-1468

SUBSCRIBED AND SWORN TO before me this 14th day of March, 1986

Carol Sue Brungardt

Notary Public

My Commission Expires: 2/11/89

STATE CORPORATION COMMISSION

MAR 17 1986  
3/17/86  
CONSERVATION DIVISION  
Wichita Kansas

Form CP-4  
Revised 08-84

HERMAN GEORGE KAISER  
Cerrow #5

NE SW NW Section 23-9S-19W  
Rooks County, Kansas

Comm: 3-9-55  
Comp: 3-18-55  
Total Depth: 3528'

<u>Casing</u>	<u>Cement</u>
8 5/8" Set @ 205'	140 sacks
5 1/2" Set @ 3523'	125 sacks

<u>FORMATION</u>	<u>DEPTH</u>
Soil, clay, rock	0 - 150
Shale	150 - 205
Shale & shells	205 - 970
Sand	970 - 1205
Shale & shells	1205 - 1225
Red bed	1225 - 1477
Anhydrite	1477 - 1512
Shale & shells	1512 - 2015
Shale & lime	2015 - 2350
Lime & shale	2350 - 3150
Lime	3150 - 3245
Lime & shale	3245 - 3300
Lime	3300 - 3486
Lime & shale	3486 - 3522
Lime (Arbuckle)	3522 - 3528

State of Kansas        )  
                          )    SS  
County of Sedgwick )

I hereby certify that the above information is true and correct to the best of my knowledge.

*Walter Elliott*

Subscribed and sworn to before me this 23rd day of March, 1955.

*Francis Warner*  
Notary Public

My commission expires: June 25, 1956

RECEIVED  
STATE CORPORATION COMMISSION

MAR 17 1986

CONSERVATION DIVISION  
Wichita, Kansas