

15-163-01680-00-00

STATE OF KANSAS
STATE CORPORATION COMMISSION

Form CP-4

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 No. Market
Wichita, Kansas

Rooks County, Sec. 23 Twp. 9S Rge. (E) 19 (W)

Location as "NE/CNW%SW%" or footage from lines SW NE NE

Lease Owner Clinton Oil Company

Lease Name Frank Cerrow Well No. 6

Office Address P. O. Box 1201, Wichita, Kansas 67201

Character of Well (completed as Oil, Gas or Dry Hole) Oil

Date well completed 4-8-19 55

Application for plugging filed 9-27 19 73

Application for plugging approved 9-28 19 73


Plugging commenced 12-22 19 73

Plugging completed 12-22 19 73

Reason for abandonment of well or producing formation Depletion

If a producing well is abandoned, date of last production 1-16 19 59

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes



Locate well correctly on above Section Plat

Name of Conservation Agent who supervised plugging of this well Leo Massey

Producing formation Arbukle O.H. Depth to top 3536 Bottom 3540 Total Depth of Well 3540 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	193'	None
				5-1/2"	3536'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Annulas - 25 sks 50/50 poz w/6% gel - 250' - 0'

5 1/2" csg - 50 sks 50/50 poz w/6% gel & 1 sk hulls - 600' - 0
30 sks gel & 4 sks hulls - 3500-600'
25 sks 50/50 poz w/6% gel - 3540 - 3500'

RECEIVED
STATE CORPORATION COMMISSION
1/3/74
JAN 3 1974
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Allied Cementing, Russell, Kansas

Address _____

STATE OF Kansas, COUNTY OF Sedgwick, ss.
Ronald E. Rowe (employee of owner) or (~~owner or operator~~) of the above-described

well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Ronald E. Rowe

P. O. Box 1201, Wichita, Kansas 67201
(Address)

SUBSCRIBED AND SWORN to before me this 2nd day of Jan., 1974

Robert L. Rathbun
Notary Public.

My commission expires _____

ROBERT L. RATHBUN
State Notary Public
Sedgwick County, Kansas
Comm. Expires Aug. 21, 1977

FORMATION RECORD

DESCRIBE EACH FORMATION DRILLED. INDICATE THICKNESS, CONTENT AND WHETHER DRY, OR OIL, GAS, OR WATER BEARING.

FORMATION	TOP	BOTTOM	FORMATION	TOP	BOTTOM
Shale	0	201			
Shale and Shells	201	580			
Shale and Sand	580	1200			
Shale and Shells	1200	1295			
Red Bed	1295	1492			
Anhydrite	1492	1528			
Shale and Shells	1528	2094			
Shale	2094	2221			
Shale and Lime	2221	3011			
Broken Lime	3011	3020			
Lime and Shale	3020	3296			
Lime K. C.	3296	3320			
Lime	3320	3532			
Arbuckle	3532	3538			
Total Depth	3540				
Rotary Tools	0	3538			
Cable Tools	3538	3540			
<p>2-28-55 CORE #1 3532'-37', Rec. 4'; 3' sh. 1' Arbuckle lm - Good show.</p> <p>2-28-55 LST #1 3499'-3538' Open 30 min. closed 20 min. Rec. 30' mud. No show. DIPS# 430#.</p> <p>3-9-55 T.D. 3538' Lumped one barrel 15% Acid on bit. Totg. 2 gal. oil per hr. No water.</p> <p>3-9-55 T.D. 3538' - Acid x 250 gal. 15%. Max Press 950# to 350# 4 hr. Swab Test Avg. 1.36 BND per hr. No water.</p> <p>3-10-55 T.D. 3538' Acid x 500 gal. 15%. Max Press 625#. No break. Testing BND .64 per hr. No water.</p> <p>3-11-55 T. D. 3540' Acid x 1000 gal. XH 10 15% Displaced on Vac. Swab 9 hrs. from bottom Avg. 1.67 BND per hr. No water.</p>					
<p>Operations Commenced: 2-15-55</p> <p>Date Spudded: 2-17-55</p> <p>Date Completed: 4-8-55</p>					
<p>Zero Point: 7.70' from center of 2" outlets on casing head.</p>					

RECEIVED
 STATE CORPORATION COMMISSION
 SEP 28 1955
 CONSERVATION DIVISION
 Wichita, Kansas