


15-163-19325-00-00

STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

Rooks County. Sec. 23 Twp. 9 Rge. 19 (SE) (W)
Location as "NE/CNW/SW" or footage from lines SW SW SE
Lease Owner Murfin Drilling Company
Lease Name Saindon Well No. 4
Office Address 617 Union Center, Wichita 2, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Oil Well
Date well completed October 7 19 54
Application for plugging filed November 24 19 58
Application for plugging approved November 25 19 58
Plugging commenced November 25 19 58
Plugging completed November 30 19 58
Reason for abandonment of well or producing formation Producing formation ran dry.



Locate well correctly on above Section Plat

If a producing well is abandoned, date of last production November 22 19 58
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Eldon Petty, Hays, Kansas
Producing formation Arbuckle Depth to top 3548 Bottom 3555 Total Depth of Well 3555 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	188'	None
				5 1/2"	3552'	2487'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Plugged back with 5 sxs. cement from 3556 to 3516'. Pull 5 1/2" to 550'. Circulate 24 sx. cement and 20 sxs. cement. Pulled 5 1/2" to 150'. Pumped in 20 sx. cement. Set 5' rock bridge from 35' to 30'. Mixed and dumped 10 sx. cement from 30' to base cellar.

RECEIVED
STATE CORPORATION COMMISSION
12/18/58
DEC 18 1958
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor Ace Pipe Pulling Company
Address Great Bend, Kansas

STATE OF Kansas, COUNTY OF Sedgwick, ss.
W. R. Murfin (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) W. R. Murfin
617 Union Center, Wichita 2, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 16th day of December, 19 58

Donna M. Matzek
Notary Public.

My commission expires March 23, 1960

PLUGGING
FILE SEC 23 T 9 R 19 W
BOOK PAGE 147 LINE 14

WELL LOG

15-163-19325-00-00

COMPANY Murfin Drilling Co.

SEC. 23 T. 9 R. 19W

FARM SAINDON NO. 4

LOC. SW SW SE

TOTAL DEPTH 3555

COUNTY Rooks KANSAS


COMM. 9-29-54

COMP. 10-8-54

SHOT OR TREATED

CONTRACTOR Murfin Drilling Co.

ISSUED



CASING

20 10
15 8 188' w/140 sx. cement
12 6
13 5 3552' w/50 sx. cement

ELEVATION 2128 DF

PRODUCTION Pot. 35 BOPD

FIGURES INDICATE BOTTOM OF FORMATIONS

Tops:

Table listing formation depths and tops. Includes entries like 'Shale - Sand' at 150, 'Topeka' at 3061, and 'Rotary Total Depth' at 3555.

RECEIVED STATE CORPORATION COMMISSION

JUN 6 1962

CONSERVATION DIVISION Wichita, Kansas

State of Kansas County of Sedgwick ss:

I, W. R. Murfin of the Murfin Drilling Company upon oath state that the above and foregoing is a true and correct copy of the log of the Saindon #4 well.

Subscribed and sworn to before me this 4th day of November 1962

My Commission Expires: 12/18/65

Handwritten signature of W. R. Murfin and Notary Public Jacqueline Zinn.