

15-163-01667-00-01

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
200 Colorado Derby Building  
Wichita, Kansas 67202

WELL PLUGGING RECORD  
K.A.R.-82-3-117

API NUMBER comp1. 7/59

LEASE NAME Boucher "A"

WELL NUMBER 1

SPOT LOCATION SE NE SW

SEC. 19 TWP. 9S RGE. 19W (S) or (W)

COUNTY Rooks

Date Well Completed 7/3/59

Plugging Commenced 1/9/86

Plugging Completed 1/9/86

TYPE OR PRINT  
NOTICE: Fill out completely  
and return to Cons. Div.  
office within 30 days.

LEASE OPERATOR Murfin Drilling Company

ADDRESS 250 N. Water, Suite 300; Wichita, KS 67202

PHONE # (316) 267-3241 OPERATORS LICENSE NO. 6033

Character of Well SWD  
(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? yes

Which KCC/KDHE Joint Office did you notify? District #6 - Hays

Is ACO-1 filed? no If not, is well log attached? yes

Producing formation Topeka/LKC/Arb. Depth to top 3112' bottom 3649' T.D. 3649'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
				8 5/8"	254'	
3/6/56 Squeezed	@ 1007' w/200 sx.			5 1/2"	3578'	
7/13/66 Squeezed	@ 1260' w/160 sx.					

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used state, the character of same and depth placed, from feet to feet each set.

Connected to 5 1/2" csg. & pumped 50 sx. 60/40 Pozmix w/6% gel & 3% CC. Followed by 250 sx. 60/40 Pozmix w/6% gel & 7 sx. hulls. Hooked up to 5 1/2" & 8 5/8" annulus & pumped 25 sx. 60/40 Pozmix w/6% gel & 1 sx. hulls. ISIP 500 psig. Connected back to 5 1/2" csg. & pumped 175 sx. 60/40 Pozmix w/6% gel, & 4 sx. hulls. ISIP - vac. Filled 5 1/2" to surface w/Redi-mix. Calc. volume pumped dwn 5 1/2" = 5305'. Calc. volume pumped dwn 5 1/2" & 8 5/8" annulus = 199'.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Murfin Drilling Company License No. 6033

Address 250 N. Water, Suite 300; Wichita, KS 67202

STATE OF Kansas COUNTY OF Sedgwick, ss.

L.O. Butner, Western Division, Prod. Manager (employee of operator) or (operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.


RECEIVED  
STATE CORPORATION COMMISSION  
2/20/86  
FEB 20 1986

By: L.O. Butner (Signature)

(Address) 250 N. Water, Suite 300

Wichita, KS 67202

SUBSCRIBED AND SWORN TO before me this 18 day of Feb., 1986



My Commission expires: 2/6/90

Kerran Redington  
Notary Public

15-163-01667-00-00

COPY

WELL LOG BUREAU KANSAS GEOLOGICAL SOCIETY  
508 East Main Street, Wichita, Kansas


Company- ISEARN DRILLING COMPANY  
Farm- Boucher No. 1

SEC. 19 T. 9 R. 19W  
SE NE SW

Total Depth. 3585  
Comm. 6-14-52 Comp. 6-25-52  
Shot or Treated.  
Contractor. Glenn R. Nye Drlg. Co.  
Issued. 9-6-52

County Rocks

KANSAS



Elevation. 2138

Production. IP 279 BO &amp; NW

## CASING:

8 5/8" 254'  
5 1/2" 3578

Figures indicate Bottom of Formations.

surface soil & clay	25
shale & shells	220
sand, shale & shells	254
shale & sand	550
shale & sand strks	1015
sand	1255
shale & redbed	1548
Anhy.	1580
shale & shells	2030
shale & lime streaks	2070
shale & lime	2360
lime & shale pyrite	
streaks	2445
lime & shale	3355
lime	3577
Arbuckle	3585
Total depth	

Scout Tops:  
Heebner 3290  
Toronto 3312  
Lansing 3329  
Arbuckle 3577

RECEIVED  
STATE CORPORATION COMMISSION

FEB 20 1986

CONSERVATION DIVISION  
Wichita, Kansas